
1. GENERAL

1.1. ATIS

D-ATIS Arrival 126.350

D-ATIS Departure 128.850

1.2. NOISE ABATEMENT PROCEDURES

As Auxiliary Power Units (APUs) generate high levels of noise and significant emissions, precautions are taken from planning to operation phase to minimize the environmental noise impact of LTFM.

It is the responsibility of airlines and ACFT handling companies to ensure that APUs are used in a manner consistent with necessity and for the absolute minimum time necessary to meet the operational needs. All inbound ACFT must be connected to a 400 Hz Fixed Electric Ground Power (FEGP) power supply within 5 minutes of entry into the parking position during docking.

All outbound ACFT are allowed to start APU earliest 10 minutes before engine start.

In areas where supported by FEGP, the use of APU and Ground Power Units (GPUs) is prohibited in LTFM.

The use of the APU and GPU for airborne Passenger Boarding Bridges (PBB) are strictly prohibited.

In circumstances where use of APU are required, electrical equipment (where city electricity is used instead of on-site generated electricity) will be used, wherever possible, in order to provide power to ACFT in order to reduce or eliminate the need for APU use.

For departures any ACFT having compliance with the noise category ICAO Annex 16, chapter 3 and 4 shall apply NADP-2 whereas all other ACFT whose noise category are in compliance with ICAO Annex 16, chapter 2 shall only apply NADP-1.

Pilots shall apply NADP-1 or NADP-2 until passing 3000'.

1.3. SURFACE MOVEMENT GUIDANCE AND CONTROL SYSTEM

1.3.1. OPERATION OF MODE S TRANSPONDERS

Advanced Surface Movement Guidance and Control System (A-SMGCS) utilizing Mode S is in service.

Activation of the Mode S transponder means selecting XPNDR, (AUTO mode if available) or the equivalent (selection of the OFF or STDBY mode will NOT activate the mode S transponder). Flight crew should also set the ACFT identification before the transponder is activated, in accordance with the ICAO defined format.

Arrival

ACFT should continue maintaining assigned Mode A code until parking on the stand. Then, Mode A code 2000 shall be set before selecting OFF or STDBY mode.

Departure

ACFT should activate the Mode-S transponder and set the assigned Mode A code as soon as ATC clearance is received.

1.3.2. OTHER INFORMATION

Flight crew shall perform the maneuver with the lowest possible thrust at the narrow parts of the apron where other parking positions affected.

Illuminated Red Stop-Bars mean "STOP". ACFT will cross Red Stop-Bars only when ATC gives permission to proceed and Stop-Bar lights are switched off.

1. GENERAL

1.4. RWY OPERATIONS

1.4.1. GENERAL

Unless otherwise authorized by ATS authority, RWYs 16L/34R and 17R/35L will not be used for landing purposes.

To optimize RWY utilization, during parallel landing take-off operation, unless otherwise specified by ATC:

- RWY 17L/35R will not be used for departure;
- RWYs 16R/34L (or 16L/34R) and 17R/35L departures will be directed to the RWYs via end-around TWY.

To optimize RWY utilization and comply with the Calculated Take-Off Time (CTOT), ATC unit can change the departure sequence.

In order to speed up departures, a parallel departure operation is implemented. In the event that the departures are concentrated on a single RWY, ATC may direct the take-off traffic to the other RWY. Pilots must be prepared to make the RWY change in order not to increase the duration of the RWY and to avoid any delay.

1.4.2. MULTIPLE LINE-UP PROCEDURES

To optimize RWY utilization, line-up instructions may be issued by TWR to more than one ACFT at different points on the same RWY, provided that:

- Intersection take-off criteria is applied;
- Minimum visibility shall be more than 3000m;
- TWR shall continuously observe the multiple line-up positions and the relevant ACFT by visual reference;
- Pilot of the succeeding ACFT shall observe the preceding ACFT on the same RWY by visual reference;
- Pilots shall be advised of the position of any essential traffic information on the same RWY;
- ACFT involved in multiple line-ups on the same RWY shall be on the same radio frequency;
- Pilots instructed to line-up shall read-back, the RWY designator, the name of the intersection (if applicable) and the number in the departure sequence;
- Wake turbulence separation is applied;
- ACFT concerned shall be identified on the A-SMGCS.

Phraseology to be used:

ATC: LINE UP AND WAIT RWY 35L, INTERSECTION B2, NUMBER 2 FOR DEPARTURE. NUMBER ONE IS B737 DEPARTING FROM B4A.

A/C: LINE UP AND WAIT RWY 35L, INTERSECTION B2, NUMBER 2.

1.4.3. RWY-IN-USE

The term "RWY-in-use" is used to indicate the RWY that, at a particular time, is considered by ATC to be the most suitable for use by the types of ACFT expected to land or take off.

Accepting a RWY stated by ATC for landing or take-off is a pilot's decision. If the pilot-in-command considers the RWY-in-use not usable for reasons of safety or performance, he shall request permission to use another RWY. This request will be met by ATC at an appropriate time. In such cases, ACFT may be subject to a long delay. ATC unit shall notify the pilot in the event that delays exceed 30 minutes.

1.4.4. PREFERENTIAL RWY SYSTEM OPERATIONS

The term "Preferential RWY System" (PRS) shall be used to indicate the RWY that, at a particular time, is considered by the ATC unit to be the most suitable for use by the ACFT expected to land at or take-off from the aerodrome, by taking into consideration ACFT performance, surface wind speed and its components. PRS operations contribute to the optimum use of airspace and aerodrome capacity.

1. GENERAL

In the PRS operations, the following wind criteria depending on the RWY surface condition shall be applied:

RWY Condition Code (RWYCC)	Tail Wind Component (MAX)
RWYCC 6/6/6	10 KT (incl)
When RWYCC is reported at least 5 for any each RWY third	5 KT (incl)

The PRS will not be available under the following circumstances:

- The instrument approach/departure procedures available for the preferred RWY(s) are not convenient for landing and/or take-off operations under the existing meteorological conditions.
- When the preferred RWY(s) are dry (RWYCC 6/6/6), the tail wind component is greater than 10 KT.
- When RWYCC is reported at least 5 for any each the preferred RWY(s) third, the tail wind component is greater than 5 KT.
- When RWYCC is reported at least 5 for any each the preferred RWY(s) third, there is a NOTAM/equivalent information (which may be included in the RCR) stating that the RWY is slippery.
- RWYCC is reported 4 or less any each the preferred RWY(s) third.
- Meteorological conditions such as heavy rainfall, thunderstorm or wind-shear has been reported on the approach or climb path of the preferred RWYs.
- Low visibility operations are in progress.

ATIS announcement when PRS operations are in progress shall be: "Preferential RWY operations are in progress".

Pilots unable to comply with PRS operations shall notify the relevant ATC unit at the time of requesting start-up clearance, at the first contact or 20 minutes in advance of the ETA (which is earlier).

1.5. CAT II/III OPERATIONS

RWYs 16R, 34L, 17L, 35R, 18 and 36 approved for CAT II/III operations, subject to serviceability of the required facilities is suitable for CAT II and III operations by operators whose minima have been formally approved by relevant Civil Aviation Authority.

During CAT II and CAT III operations, RWYs 16L/34R and 17R/35L will not be used for landing and take-off.

For CAT II and CAT III operations, special aircrew and ACFT certification required.

During CAT II and CAT III operations, special ATC procedures (ATC Low Visibility Procedures) will be applied. Pilots will be informed when these procedures are in operation by ATIS or RTF.

Arriving ACFT

Advanced Surface Movement Guidance and Control System (A-SMGCS) is available and all RWY exits will be illuminated. Pilots should select the first convenient exit.

Departing ACFT

Advanced Surface Movement Guidance and Control System (A-SMGCS) is available and ATC will request departing ACFT to use the CAT II/III holding points.

1. GENERAL

1.6. FLIGHT PROCEDURES

"Super" or "Heavy" turbulence category ACFT at first contact with each sector shall report: Call Sign + "SUPER" or "HEAVY" + ...

1.6.1. SIMULTANEOUS INDEPENDENT PARALLEL APPROACHES/DEPARTURES

To optimize RWY utilization and increase air traffic efficiency, simultaneous independent parallel approaches are in progress daily (24 hours) and are subject to the availability of ILS approaches.

Simultaneous independent parallel departures are in progress daily (24 hours).

1.6.2. PROCEDURES FOR SIMULTANEOUS INDEPENDENT PARALLEL APPROACHES

ATC will clear the ACFT to the ILS approach for the relevant RWY before the Initial Approach Fix (IAF). A sample of ATC instruction is stated below:

"(Call-sign) CLEARED FOR ILS APPROACH RWY..."

As soon as such an instruction is received, the ACFT shall completely follow the cleared ILS approach (including the P-RNAV TRANSITION) for the relevant RWY.

ACFT without P-RNAV approval (RNAV (GNSS)) may lose the sequence and be subject to a delaying action. The ACFT concerned will be radar vectored to final, or cleared/vectored to a point from where approach can be made.

1.6.3. DEVIATION TOWARDS NTZ

When an ACFT is observed to have not established on the appropriate LOC course or deviated from its course towards the NTZ, monitoring controller will instruct the ACFT to return immediately to the correct LOC course with the following radiotelephony phraseology:

"YOU HAVE CROSSED THE LOCALIZER, TURN LEFT (or RIGHT) IMMEDIATELY AND RETURN TO THE LOCALIZER".

1.6.4. BREAK-OUT MANEUVER

In the event that, an ACFT is observed to penetrate the NTZ, monitoring controller will instruct the ACFT on the adjacent LOC course to immediately turn and climb to the assigned heading and altitude by overriding the relevant Tower/Approach frequencies with the following radiotelephony phraseology:

"TURN LEFT (or RIGHT) HEADING (degrees) IMMEDIATELY TO AVOID TRAFFIC AND CLIMB TO (altitude)".

ATC will not give instructions for break-out maneuvers below 750' AMSL.

1.6.5. RWY ASSIGNMENT

When the simultaneous independent parallel approaches/departures are in progress, appropriate use of RWYs is subject to ATC discretion in order to ensure safe and orderly flow of the traffic.

For tactical reasons and to increase air traffic efficiency, ATC may change the assigned landing RWY with the notification of the pilot prior to, clearing the ACFT to the relevant Initial Approach Fix (SADIK, IMREN, DIVDI or INSTA).

1.6.6. PILOT NOTIFICATIONS TO OPERATIONS

Simultaneous independent parallel approaches/departures to the relevant RWYs will be broadcasted on ATIS during the active period like as:

- "Simultaneous independent parallel ILS approaches in progress on RWY 34L and RWY 35R"; or
- "Simultaneous independent parallel departures in progress".

1. GENERAL

1.6.7. THE MANDATORY IMPLEMENTATION OF RNAV (GNSS) SIDS AND STARS

RNAV (GNSS) SID/STAR procedures are mandatory for P-RNAV approved ACFT equipped with PBN/D1-D2-O1-O2. Therefore, the P-RNAV approved ACFT arriving/departing to/from LTFM are required to flight plan or submit a Change Message (CHG) concerning the route section of their RPLs as described below.

1. GNSS based RNAV STARS for LTFM starts from the waypoint/fixes designated as RIXEN, ATPIX, ERSEN, SISPI, INBET, DRAMO and RILEX. These waypoints/fixes shall be the last element of the flight planned routes for the P-RNAV approved ACFT as illustrated below:

- A flight planned route for the arrivals to LTFM via AFYON VOR (KFK);

EXAMPLE: UB545 KFK M855 SISPI

2. GNSS based RNAV SIDs for LTFM ends at the waypoint/fixes, designated as MAKOL, OSMEV, ASMAP, RATVU, IVGUS, BARPE, VADEN, TUDBU and IBLAL. These waypoints/fixes shall be the first element of the flight planned routes for the P-RNAV approved ACFT as illustrated below:

- A flight planned route for the departures from LTFM via OSMEV;

EXAMPLE: OSMEV T641

The LTFM departures destined to LTBA or LTFJ are excepted from this mandatory implementation. The conventional procedures published on IST 1N & 1P DEPS (30-3W9) chart are available for these flights.

1.7. TAXI PROCEDURES

Wingtip clearance is under flight crew responsibility.

"Reduced engine taxi" not allowed during the RWY crossing.

1.8. OTHER INFORMATION

Flight crew should inform Ground Control if the ACFT livery differs from the ACFT callsign.

Birds.

All ACFT de-icing positions on De-icing 1, 2, 3, 4 and 5 Aprons to be used as penalty areas when needed.

Helicopter landing and take-off point is on TWY G2 at Southeast of the aerodrome (coordinates: N41 15.2 E028 45.3).

2. ARRIVAL

2.1. SPEED RESTRICTION

All speeds depicted on the STARS are applied for ATC separation purposes and mandatory. ACFT unable to conform to these speeds shall inform ATC and state what speeds to be used. The speed restrictions are to be flown as accurately as possible (accurate within 5 KT). ACFT are required to comply with the level and speed restrictions depicted on IAC.

2.2. POINT MERGE SYSTEM (PMS)

LTFM STARS are based on PMS. Each STAR contains segments forming a curved sequencing leg equidistant from the Merge Point (MP).

The sequencing legs of PMS vertically separated, with the one closer to the MP located above the one further away.

When descend clearance has been transmitted by ATC, ACFT have to reach a defined altitude and speed to fly the sequencing legs.

Merging to the next segment is then achieved by direct clearance to the MP.

PMS allows for efficient shortening or stretching of the ACFT arrival path depending on the traffic situation at hand.

2. ARRIVAL

LTFM MPs that are at the same time designated as Initial Approach Fixes are SADIK, IMREN, DIVDI and INSTA.

Arriving ACFT established on the STAR may expect clearance direct to the relevant MP only when the traffic permits.

Succeeding ACFT will subsequently be cleared direct to the MP when sufficient spacing to preceding ACFT is obtained.

Hence, a precise sequencing can be achieved whilst the ACFT maintain own navigation (LNAV).

2.3. HOLDINGS AT ARRIVAL PHASE

In the event that delays on holdings at arrival phase exceed 20 minutes, ATC unit shall transmit EXPECTED APPROACH TIME to the ACFT concerned.

2.4. MINIMUM RWY OCCUPANCY TIME

Arrival ACFT at first contact with TWR shall report: "Call Sign + RWY".

Landing ACFT shall vacate the RWY as quickly as possible in order to ensure minimum RWY occupancy time and reduce go around due to an occupied RWY.

When RWY condition is dry, ACFT should vacate the RWY via rapid exits stated in the table below.

	Distance (m) from THR to Rapid Exit TWY											
ACFT	RWY 16R		RWY 17L		RWY 18		RWY 34L		RWY 35R		RWY 36	
Category	Exit		Exit		Exit		Exit		Exit		Exit	
Medium	A6A		C7		G10		A7A		C8		G13	
	1785		2075		1845		1785		1785		1785	
Heavy	A6A	A5A	C7	C6	G10	G9A	A7A	A8A	C8	C9	G13	G14
	1785	2185	2075	2375	1845	2245	1785	2085	1785	2145	1785	2085

When deemed it is not possible/appropriate to use the rapid exit TWYs recommended in the table above by the pilot, due to flight safety requirements, the pilot shall inform TWR controller as soon as possible.

Unless otherwise instructed by ATC:

- Landing ACFT on RWY 17L, shall vacate the RWY to the LEFT, continue on TWY C and contact with Ground 3 on 122.6 MHz without waiting any instruction by TWR controller.
- Landing ACFT on RWY 35R, shall vacate the RWY to the RIGHT, continue on TWY C and contact with Ground 3 on 122.6 MHz without waiting any instruction by TWR controller.
- Landing ACFT on RWY 18, shall vacate the RWY to the RIGHT, continue on TWY G and contact with Ground 4 on 124.425 MHz without waiting any instruction by TWR controller.
- Landing ACFT on RWY 36, shall vacate the RWY to the LEFT, continue on TWY G and contact with Ground 4 on 124.425 MHz without waiting any instruction by TWR controller.
- Landing ACFT on RWY18/36, should not vacate the RWY via 90° turn G11 and G12 TWYs.
- Landing ACFT on RWY 16R/34L, shall remain on TWR frequency due to the reason that, crossing RWY 16L/34R is subject to red stop-bars and ATC permission and shall not switch on Ground frequency.

ACFT vacating a RWY via rapid exit TWY has the priority at the intersection of the TWYs, over the ACFT taxiing on other TWYs. Therefore, pilots shall be cautious about this priority and unless otherwise instructed by ATC, shall give way to the ACFT vacating a RWY via one of the rapid exit TWYs.

3. DEPARTURE

3.1. ATC CLEARANCE PROCEDURES

Pilots of departing ACFT shall receive the ATC clearance via DCL system, unless otherwise specified by ATC.

If unable to receive ATC clearance via DCL, the flight crew shall contact with Clearance Delivery 121.700 MHz for ATC clearance and at first contact shall report; "Call Sign + Stand Position + Code confirming ATIS message received (e.g. Information A)". There may be delays while transmitting ATC clearances by radiotelephony.

3.2. DE-ICING

Entrance to De-icing 1 Apron de-icing stands is from North side (as ACFT facing South). Entrance to De-icing 2, 3 and 4 Aprons de-icing stands is from South side (as ACFT facing North). Entrance to De-icing 5 Apron de-icing stands is from West side (as ACFT facing East). Entrance to any de-icing stand from opposite site is allowed only by ATC instructions and provided that a Follow-me vehicle is available.

3.3. START-UP PROCEDURES

Flight crews, while requesting engine start-up clearance, should have completed their preparations for departure, according to the Calculated Take-off Time (CTOT) taking the average taxi time (16 minutes) into account. Otherwise ATC unit will not give push-back and start-up clearance.

Flight crews intending to start up at parking positions shall get clearance from the ATC unit.

Engine testing shall be performed at the Motor Test Apron. Prior to engine testing, ACFT shall contact Ground Control on frequency 126.3 MHz.

Flight crews intending to cross bleed start shall advise ATC unit before push-back as:

"Call sign + parking position + request cross bleed start".

ACFT engine shall not be start up in hangars, closed or semi closed areas.

ACFT engine shall not be start up while powered, or towed passenger steps or passenger boarding bridges are connected to the ACFT.

In order to prevent blocking TWY with a towed ACFT waiting for hangar doors to be opened, ACFT towing from open stands to closed hangars shall not commence unless hangar doors are opened before.

3.4. PUSH-BACK PROCEDURES

Traffic with transponder off or not active will not be allowed for push-back.

Traffic cleared for push-back and start-up must start push-back within 1 minute at least. Otherwise ATC unit will give estimated start-up time.

It is forbidden to make power-back through using engines' reverse thrust.

ACFT shall push-back from the parking areas to the nearest TWY centerlines, unless otherwise specified by ATC.

ACFT relocation between stands or from stand to hangar is not allowed during LVO.

3. DEPARTURE

3.5. MINIMUM RWY OCCUPANCY TIME

To optimize the RWY utilization, flight crews shall complete all checklists prior to line-up clearance and be ready for immediate take-off. When ACFT is at the RWY holding point, pilots should commence line-up and take-off roll immediately after take-off clearance is issued by ATC.

When ACFT is already lined-up on RWY, pilots should commence take-off roll immediately after take-off clearance is issued by ATC. Pilots are expected to react take-off clearances within 10 seconds.

For departure ACFT, time-based wake turbulence separation minima are used in accordance with the ICAO WTG - Wake Turbulence Groups classification. Pilots must be ready for take-off in order not to increase RWY occupancy time and to avoid any delay.

The filling of the flight plan and the phraseology remain unchanged.


Pilots unable to comply with these requirements shall notify ATC before entering the RWY, otherwise ATC may instruct the ACFT to vacate the RWY and re-sequence in order to prevent excessive RWY occupation.

JEPPESSEN İSTANBUL, TÜRKİYE
16 SEP 22 **30-2**
RNAV STAR


D-ATIS Arrival 126.350	Apt Elev 325
---------------------------	-----------------

Alt Set: hPa Trans level: By ATC
1. RADAR required. 2. P-RNAV approval required
otherwise advise ATC.

3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final, or cleared/ vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform STANBUL CONTROL/ YESLIKOY APPROACH on initial contact. Otherwise, at first contact with YESLIKOY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will be given before IAF, when received follow and execute IAP (including the P-RNAV TRANSITION). 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATIS as soon as possible. 8. Descend as cleared.



© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.



LTFM/IST
ISTANBUL

16 SEP 22 (30-2B)

JEPPESEN

ISTANBUL,
TÜRKİYE
RNAV STAR

DATIS Arrival

126.350

Api Elev

325

Alt Set: Hpa. Trans level: By ATC
1. RADAR required. 2. P-RNAV approval required otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action.
The ACFT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESILKOY APPROACH on initial contact. Otherwise, at first contact with YESILKOY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will be given before IAP, when received follow and execute IAP (including the P-RNAV TRANSITION). 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
8. Descend as cleared.

EREN 2P [ERSE2P]
SISP1 2P [SISP2P]
RNAV (GNSS) ARRIVALS
(RWYS 16R, 17L, 18)

CAUTION

1. Should there be flight level restrictions at or above the Transition Level, do not set local QNH until descending below the lowest flight level restriction. 2. When cleared ILS for RWYs 16R, 17L or 18, do not engage ILS before Localizer Intercept points PEVUD, TIGSU or KORQU. 3. ATC may clear the ACFT to the Holding Point FM166 when required. 4. Minimum rate of descent at Holding Points 1000 FT/MIN. 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

Before ENRAW:

It already cleared to 9000 continue via filed/cleared STAR. Otherwise MAINTAIN last assigned level for 3 minutes, then descent to 9000 continue via filed/cleared STAR.

At or after ENRAW:

Continue via filed/cleared STAR by adhering to published profile until ILS (IAF). Then execute the relevant instrument approach procedure for RWY 16R and land. If available call telephone number 0090 212 405 01 21.

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

STAR

ERSEN 2P

ERSEN - FM551 - EPEKI (K280; FL280) - FM552 - FM553 (FL210) - PUDET (K230; FL190; FL170) - FM553 - FM556 - FM595 (FL130; FL200) - ENRAW (K230; 9000) - FM573 - FM760 - FM761 - FM762 - FM763 - FM764 (9000) - FM765 - FM766 - FM767 - INSTA (K220; 3000).

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

ROUTING

ERSEN - FM551 - EPEKI (K280; FL280) - FM552 - FM553 (FL210) - PUDET (K230; FL190; FL170) - FM553 - FM556 - FM595 (FL130; FL200) - ENRAW (K230; 9000) - FM573 - FM760 - FM761 - FM762 - FM763 - FM764 (9000) - FM765 - FM766 - FM767 - INSTA (K220; 3000).

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

SISP1 2P

SISP1 - FM650 - FM651 (K280; FL280) - FM652 - LECK1 - FM553 (FL210) - PUDET (K230; FL190; FL170) - FM553 - FM556 - FM595 (FL130; FL200) - ENRAW (K230; 9000) - FM573 - FM760 - FM761 - FM762 - FM763 - FM764 (9000) - FM765 - FM766 - FM767 - INSTA (K220; 3000).

LOST COMMS


LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS

LOST COMMS



CHANGES: Country name.

LTFM/IST
ISTANBUL

JEPESEN
16 SEP 22 30-2C

ISTANBUL, TURKIYE
RNAV STAR

D-ATIS Arrival
126.350
Apt Elev
325

Alt Set: hpa. Trans level: By ATC
1. RADAR required. 2. P-RNAV approval required otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESLIKOV APPROACH on initial contact. Otherwise, at first contact with YESLIKOV APPROACH report only call sign. 5. IAP clearance for the relevant RWY will be given before IAP, when received follow and execute IAP (including the P-RNAV TRANSITION). 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATIS as soon as possible.
8. Descend as cleared.

DRAMO 2B [DRAM2B]
INBET 2B [INBE2B]
RNAV (GNSS) ARRIVALS
(RWYS 16R, 17L, 18)

ISTANBUL
Sabiha Gökçen Intl
117

CAUTION


1. Should there be flight level restrictions at or above the Transition Level, do not set local QNH level descending below the lowest flight level restriction. 2. When cleared ILS for RWYs 16R, 17L or 18, do not engage ILS before Localizer Intercept points PEVUD, TIGSU or KORQU. 3. ATC may clear the ACFT to the Holding Point FM166 when required. 4. Minimum rate of descent at Holding Point 1000 FT/MIN. 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

Before FM757:
If already cleared to 9000 continue via filed/cleared STAR. Otherwise MAINTAIN last assigned level for 3 minutes, then descent to 9000 continue via filed/cleared STAR.

At or after FM757:
Continue via filed/cleared STAR by adhering to published profile until INSTA (IAF). Then execute the relevant instrument approach procedure for RWY 16R and land. If available call telephone number 0090 212 405 01 21.

ROUTING

STAR
DRAMO 2B
FM753 (K230) - FL270 - AGBET - FM751 (FL220) - FL200 - FM752 - FM758 (K230) 9000 - FM754 - FM755 (FL140) - FL200 - FM756 - FM757 - FM765 - FM766 - FM767 - INSTA (K220) 3000 -
INBET 2B
INBET - LEKMI (K280) FL270 - GUBUL - FM751 (FL200) - FM752 - FM753 (K230) - FM754 - FM755 (FL140) - FL200 - FM756 - FM757 - FM758 (K230) 9000 - FM768 - FM761 - FM762 - FM765 - FM764 (9000) - FM765 - FM766 - FM767 - INSTA (K220) 3000 -



LTFM/IST
ISTANBUL

16 SEP 22 (30-2D)

JEPPESEN


ISTANBUL
TURKIYE
RNAV STAR

D-ATIS Arrival
126.350

Apt Elev
325

All Set: hPa. Trans level: By ATC
1. RADAR required. 2. P-RNAV approval required
otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the
sequence and be subject to a delaying action.
The ACFT concerned will be RADAR vectored to final,
or cleared/vectored to a point from where approach
can be made. 4. If unable to comply the RNAV
procedure, Inform ISTANBUL CONTROL/YESILKOY
APPROACH on initial contact. Otherwise, at first
contact with YESILKOY APPROACH report only call
sign. 5. IAP clearance for the relevant RWY will be
given before IAF, when received follow and execute
IAP (including the P-RNAV TRANSITION). 6. The use
of a STAR designator without a cleared level does not
authorize the ACFT to descend on the STAR vertical
profile. 7. In the event that pilot assesses a
published level or speed restriction cannot be met,
must inform ATC as soon as possible.
8. Descend as cleared.

DRAMO 2P [DRAM2P]
INBET 2P [INBET2P]
RNAV (GNSS) ARRIVALS
(RWYS 16R, 17L, 18)



CAUTION


1. Should there be flight level restrictions at or above the Transition Level, do not set local ONH until descending below the lowest flight level restriction. 2. When cleared ILS for RWYs 16R, 17L or 18, do not engage ILS before localizer intercept points PEVUD, TIGSU or KORQU. 3. ATC may clear the ACFT to the Holding Point ENLEC when required. 4. Minimum rate of descent at Holding Points 1000 FT/MIN. 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

Before FMS56:
1. Descend to 11000 continue via filed/cleared STAR. Otherwise MAINTAIN the assigned level for 3 minutes, then descend to 11000 continue via filed/cleared STAR.
At or after FMS56:
Continue via filed/cleared STAR by adhering to published profile until DIVDI (IAF). Then execute the relevant instrument approach procedure for RWY 17L and land. If available call telephone number 0090 212 465 01 21.

STAR	ROUTING
DRAMO 2P	DRAMO (K280; FL270-) - AGBET - FM751 (FL220-; FL200+) - FM752 - FM753 (K250) - FM754 - FM755 - FM756 - FM757 - FM758 - FM759 - FM760 - FM761 - FM762 - FM763 - FM764 - FM765 - FM766 - FM767 - FM768 - FM769 - FM770 - FM771 - FM772 - FM773 - FM774 - FM775 - FM776 - FM777 - FM778 - FM779 - FM780 - FM781 - FM782 - FM783 - FM784 - FM785 - FM786 - FM787 - FM788 - FM789 - FM790 - FM791 - FM792 - FM793 - FM794 - FM795 - FM796 - FM797 - FM798 - FM799 - FM800.
INBET 2P	INBET - LEKMI (K280; FL270-) - GUBUL - FM751 (FL220-; FL200+) - FM752 - FM753 (K250) - FM754 - FM755 - FM756 - FM757 - FM758 - FM759 - FM760 - FM761 - FM762 - FM763 - FM764 - FM765 - FM766 - FM767 - FM768 - FM769 - FM770 - FM771 - FM772 - FM773 - FM774 - FM775 - FM776 - FM777 - FM778 - FM779 - FM780 - FM781 - FM782 - FM783 - FM784 - FM785 - FM786 - FM787 - FM788 - FM789 - FM790 - FM791 - FM792 - FM793 - FM794 - FM795 - FM796 - FM797 - FM798 - FM799 - FM800.

AI: Sep18a. Trans level: By ATC
1. RADAR required. 2. P-RNAV approval (required otherwise) advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final or cleared/vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESLIKOY APPROACH on initial contact. Otherwise, at first contact with YESLIKOY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will given before IAF, when received follow and execute the STAR designator without a cleared level does authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met must inform ATC as soon as possible.
8. Descend as cleared.

AI: Sep18a. Trans level: By ATC
1. RADAR required. 2. P-RNAV approval required otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final or cleared/vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESLIKOY APPROACH on initial contact. Otherwise, at first contact with YESLIKOY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will given before IAF, when received follow and execute the STAR designator without a cleared level does authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met must inform ATC as soon as possible.
8. Descend as cleared.




- CAUTION**
1. Should there be flight level restrictions at or above the Transition Level, do not set Local QNH until descending below the lowest flight level restriction.
 2. When cleared ILS for RWYs 34L, 35R or 36, do not engage ILS before Localizer Intercept points OGIBI, GAPDI or GUNCE.
 3. ATC may clear the ACFT to the Holding Point BOZDE when required.
 4. Minimum rate of descent at Holding Points 1000 FT/MIN.
 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

- | | | |
|---------------------------|-----------------|-------------------------------------|
| D-ATIS Arrival
126.350 | Apt Elev
325 | Alt Set: hPa
Trans Level: By ATC |
|---------------------------|-----------------|-------------------------------------|
1. RADAR required.
 2. P RNAV approval required otherwise advise ATC.
 3. ACFT without P RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made.
 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESILKOY APPROACH on initial contact. Otherwise, at first contact with YESILKOY APPROACH report only call sign.
 5. IAP clearance for the relevant RWY will be given before IAF, when received follow and execute IAP (including the P RNAV TRANSITION).
 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile.
 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
 8. Descend as cleared.

HOLDING OVER



ATPIX 2A [ATPIX 2A]
ERSEN 2N [ERSEN 2N]
RIXEN 2N [RIXEN 2N]
RNAV (GNSS) ARRIVALS
(RWYS 34L, 35R, 36)



STAR	ROUTING
ATPIX 2A	ATPIX (K280; FL280-) - FM420 (FL230-; FL210+) - FM421 - FM422 (K230) - FM423 - FM424 (FL140-; 12000+) - FM425 - FM426 (K230; 10000) - FM430 - FM431 - FM432 - FM433 - FM434 (10000) - FM435 - FM436 - SADIK (K220; 7000-; 5000+).
ERSEN 2N	ERSEN - TUSCA (K280; FL280-) - PATHO - GEFME - PAZAR - FM424 (FL140-; 12000+) - FM425 - FM426 (K230; 10000) - FM430 - FM431 - FM432 - FM433 - FM434 (10000) - FM435 - FM436 - SADIK (K220; 7000-; 5000+).
RIXEN 2N	RIXEN (K250; FL230-) - GINLI - ATVAS - FM920 (FL170-; FL150+) - FM921 - FM426 (K230; 10000) - FM430 - FM431 - FM432 - FM433 - FM434 (10000) - FM435 - FM436 - SADIK (K220; 7000-; 5000+).

LTFM/IST
ISTANBUL


JEPPESEN
16 SEP 22 (30-2G)

ISTANBUL, TURKIYE
RNAV STAR

D-ATIS Arrival	ApT Elev	Alt Set: hPa	Trans level: By ATC
126.350	325		

1. RADAR required. 2. P-RNAV approval required otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final or cleared/vectored to a point from where approach can be made.
4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESLIKÖY APPROACH on initial contact. Otherwise, at first contact with YESLIKÖY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will be given before IAF, when received follow and execute IAP (including the P-RNAV TRANSITION). 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
8. Descend as cleared.

ATPIX 2N RNAV (GNSS) ARRIVAL
[ATP12N]
(RWYS 34L, 35R, 36)



CAUTION

1. Should there be flight level restrictions at or above the Transition Level, do not set Local QNH until descending below the lowest flight level restriction. 2. When cleared ILS for RWYs 34L, 35R or 36, do not engage ILS before Localizer intercept points OGI1, GAPDI, GUNCE. 3. ATC may clear the ACFT to the Holding Point FM736, when required. 4. Minimum rate of descent at Holding Point 1000 FT/MIN. 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

ROUTING

ATPIX (K280: FL280+) - FM420 (FL230+) - FM421 - FM422 (K250) - FM423 (K230: 10000) - FM921 - LIZTA - FM908 - FM827 - FM830 (K230: 10000) - FM831 - FM832 - FM833 - FM834 (10000) - FM835 - FM836 - IMREN (K220: 4000+).

LOST COMMS

Before FM827: If already cleared to 10000 continue via filed/cleared STAR. Otherwise MAINTAIN last assigned level for 3 minutes, then descent to 10000 continue via filed/cleared STAR.


At or after FM827: Continue via filed/cleared STAR by adhering to published profile until IMREN (IAF). Then execute the relevant instrument approach procedure for RWY 34L and land. If available call telephone number 0090 212 465 01 21.

CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-2H) RNAV STAR



CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPPESSEN
16 SEP 22 (30-2J)

ISTANBUL, TURKIYE
RNAV STAR

1. RADAR required. 2. P-RNAV approval required otherwise advise ATC. 3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made. 4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESILKOY APPROACH on initial contact. Otherwise, at first contact with YESILKOY APPROACH report only call sign. 5. IAP clearance for the relevant RWY will be given before IAF, when received follow and execute IAP (including the P-RNAV TRANSITION). 6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile. 7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible. 8. Descend as cleared.

D-ATIS Arrival	Apt Elev	Alt Set: hPa	Trans level: By ATC
126.350	325		

DRAMO 2A [DRAM2A], INBET 2A [INBE2A]
RNAV (GNSS) ARRIVALS
(RWYS 34L, 35R, 36)



CAUTION

1. Should there be flight level restrictions at or above the Transition Level, do not set local QNH until descending below the lowest flight level restriction. 2. When cleared ILS for RWYs 34L, 35R or 36 do not engage ILS before Localizer Intercept points OGBI, GAPDI or GUNCE. 3. ATC may clear the ACFT to the Holding Point FM736 when required. 4. Minimum rate of descent at Holding Points 1000 FT/MIN. 5. The ACFTs are required to plan their descent to comply with the level and speed restrictions depicted on the procedure. If unable will lose the sequence and be subject to a delaying action.

STAR	ROUTING
DRAMO 2A	DRAMO (K280; FL250+) - ACBET (FL1200+; FL200+) - FM720 - FM721 (K250) - FM722 - FM723 (FL140+; 12000+) - FM724 - FM725 (K250; 9000) - FM730 - FM731 - FM732 - FM733 - FM734 (9000) - FM735 - FM736 - IMREN (K220; 4000+).
INBET 2A	INBET (K280; FL250+) - LEKMI - GUBUL (K250; FL170+; FL150+) - FM723 (FL140+; 12000+) - FM724 - FM725 (K230; 9000) - FM731 - FM732 - FM733 - FM734 (9000) - FM735 - FM736 - IMREN (K220; 4000+).


LTfM/IST
ISTANBUL

JEPPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-2K)
RNAV STAR

D-ATIS Arrival
126.350
Apt Elev
325
Alt Set: hPa Trans level: By ATC

1. RADAR required. 2. P-RNAV approval required otherwise advise ATC.
3. ACFT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACFT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made.
4. If unable to comply the RNAV procedure, inform ISTANBUL CONTROL/YESILKOY APPROACH on initial contact. Otherwise, at first contact with YESILKOY APPROACH report only call sign, execute IAP (including the P-RNAV TRANSITION).
5. IAP clearance for the relevant RWY will be given before IAF, when received follow and execute IAP (including the P-RNAV TRANSITION).
6. The use of a STAR designator without a cleared level does not authorize the ACFT to descend on the STAR vertical profile.
7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
8. Descend as cleared.

RILEX 2N RNAV (GNSS) ARRIVAL
[RILE2N]
(RWYS 34L, 35R, 36)



CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

1. RADAR required, 2. P-RNAV approval required to authorize advise ATIS.
3. ACT without P-RNAV approval may lose the sequence and be subject to a delaying action. The ACT concerned will be RADAR vectored to final, or cleared/vectored to a point from where approach can be made.
4. If there is to comply the P-RNAV procedure, inform ISTABUL CONTROL, TESTISY APPROACH on initial contact. Otherwise, at first contact with TESTISY APPROACH report only call sign.
5. IAP clearance for the relevant RWY will be given before IAP, when received below and execute IAP (including the P-RNAV TRANSITION).
6. The use of a STAR designator without a cleared level does not authorize the ACT to descend on the STAR vertical profile.
7. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATIS as soon as possible.
8. Descend as cleared.




LTFM/IST
ISTANBUL

JEPPESEN ISTANBUL, TURKIYE
16 SEP 22 30-3
RNAV SID

YESILKOY Approach/ Radar (DEP) 131.125 132.050	Api Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

MAKOL 4F [MAKOL4F]
OSMEV 4F [OSME4F]
RNAV (GNSS) DEPARTURES
(RWYS 16L/R)



CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPPESEN
16 SEP 22 (30-3A)

ISTANBUL, TURKIYE
RNAV SID

YESLIKÖY Approach/ Radar (DEP) 131.125 132.050	Api Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESLIKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

MAKOL 4G [MAK04G]
OSMEV 4G [OSME4G]
RNAV (GNSS) DEPARTURES
(RWYS 17L/R)




LTFM/IST
ISTANBUL

JEPPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-3B)
RNAV SID

YESIKOY Approach/ Radar (DEP) 131.125 132.050	Api Elev 325	Trans alt: 12000
--	-----------------	------------------

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

MAKOL 4H [MAKO4H]
OSMEV 4H [OSME4H]
RNAV (GNSS) DEPARTURES
(RWY 18)



CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPPESEN
16 SEP 22 (30-3C)

ISTANBUL, TURKIYE
RNAV SID

YESILKOY	Appt Elev	Trans alt: 12000
Approach/ Radar (DEP)	131.125	325
	132.050	

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.


MAKOL 4C [MAKO4C]
OSMEV 4C [OSME4C]
RNAV (GNSS) DEPARTURES
(RWYS 34L/R)



LTFM/IST
ISTANBUL

YESILKÖY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required. 2. P RNAV approval required otherwise advise ATC. 3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure. 4. Check ATIS for current frequency. 5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile. 6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible. 7. No Turns Prior to DER.	MAKOL 4D [MAKOL4D] OSMEV 4D [OSME4D] RNAV (GNSS) DEPARTURES (RWYS 35L/R)
---	---



CHANGES: Country name.


LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22
30-3E
ISTANBUL, TURKIYE
RNAV SID

YESILKOY	Appt Elev	Trans alt: 12000
Approach/ Radar (DEP)		
131.125	325	
132.050		

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

MAKOL 4E [MAKOL4E]
OSMEV 4E [OSME4E]
RNAV (GNSS) DEPARTURES
(RWY 36)



CHANGES: Country name.


© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

YESILKÖY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designer. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designer without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4F [ASMAAF]
RATVU 4F [RATVAF]
RNAV (GNSS) DEPARTURES
(RWYS 16L/R)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.	
Gnd speed-KT	75 100 150 200 250 300
5.0% V/V (fpm)	360 506 760 1013 1266 1519
Initial climb clearance 4000	
SID	ROUTING
ASMAP 4F	(900+) - FM047 (K240-; 2100+) - FM054 -
ASGAX	ASGAX - VRACA - ROCHE - NASNA -
NENVI	NENVI - IBSIN - LECKI - VICEN - ASMAP.
RATVU 4F	(900+) - FM047 (K240-; 2100+) - FM054 -
ASGAX	ASGAX - VRACA - EVMOG - GUPTU -
XESRA	XESRA - RATVU.

LTFM/IST
ISTANBUL

16 SEP 22

JEPRESEN
(30-3G)

ISTANBUL, TURKIYE
RNAV SID

YESILKOY


Approach/ Radar (DEP)
131.125
132.050

Apf Elev
325

Trans alt: 12000

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4T [ASMA4T]
RATVU 4T [RATV4T]
RNAV (GNSS) DEPARTURES
(RWYS 16L/R)
EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 06



CHANGES: Country name.

© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-3H) RNAV SID

YESILKÖY

Approach/ Radar (DEP)	Apt Elev	Trans alt:
131.125	325	12000
132.050		

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4G [ASMA4G]
RATVU 4G [RATV4G]
RNAV (GNSS) DEPARTURES
(RWYS 17L/R)



CHANGES: Country name.

© JEPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22

(30-31)

YESILKÖY

ISTANBUL, TÜRKİYE
RNAV SID


Approach/ Radar (DEP)
131.125
132.050

Appt Elev
325

Trans alt: 12000

1. RADAR required.
2. RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4U [ASMA4U]
RATVU 4U [RATV4U]
RNAV (GNSS) DEPARTURES
(RWYS 17L/R)
EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 06



CHANGES: Country name.

© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-3K) RNAV SID

YESILKÖY

Approach/ Radar (DEP)	Apt Elev	Trans alt:
131.125	325	12000
132.050		

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4H [ASMA4H]
RATVU 4H [RATV4H]
RNAV (GNSS) DEPARTURES
(RWY 18)



CHANGES: Country name.

© JEPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22

JEPRESEN
(30-31)

ISTANBUL, TURKIYE
RNAV SID

YESILKOY


Approach/ Radar (DEP)
131.125
132.050

Appt Elev
325

Trans alt: 12000

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4V [ASMA4V]
RATVU 4V [RATV4V]
RNAV (GNSS) DEPARTURES
(RWY 18)
EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 06



CHANGES: Country name.


© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

JEPPESEN ISTANBUL, **TÜRKİYE**
16 SEP 22 **30-3M** **RNAV SID**

RNAV SID

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESIKOV. Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No turns prior to DER.

- ASMAP 4C [ASMA4C]
RATVU 4C [RATV4C]
RNAV (GNSS) DEPARTURES
(RWYS 34L/R)



YESLIKOV		
Approach/ Radar (DEP)		
131,125	Apt Elev	
132,050	325	Trans alt: 12000


1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DRR.

ASMAP 4Q RNAV (GNSS)

[ASMA4Q]

(RWYS 34L/R)

EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 24



CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL

JEPESEN ISTANBUL, TURKIYE
16 SEP 22 (30-3P) **RNAV SID**

YESTIKOY	APt Elev	Trans alt:
Approach/ Radar (DEP) 131.125 132.050	325	12000

1. RADAR required.
2. RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESTIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

**ASMAP 4D [ASMA4D]
RATVU 4D [RATV4D]
RNAV (GNSS) DEPARTURES
(RWYS 35L/R)**



CHANGES: Country name.

© JEPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22

JEPRESEN
(30-30)

ISTANBUL, TURKIYE
RNAV SID

YESILKOY

Approach/ Radar (DEP)	Appt Elev	Trans alt:
131.125	325	12000
132.050		

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.


ASMAP 4R RNAV (GNSS)

DEPARTURE

[ASMA4R]

(RWYS 35L/R)

EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 24



This SID requires a minimum climb gradient of 5.0% (304 Per NM) up to 8000.						
Gnd speed-KT	75	100	150	200	250	300
5.0% V/V (fpm)	380	506	760	1013	1266	1519

Initial climb clearance 5000

ROUTING

(760+) - FM012 (K240+) - 1750+ - FM020 - FM021 - ELNUG - MIKOC - FILFU - FM043 - ROCHE - NENVI - IBSIN - LECKI - VICEN - ASMAP.

CHANGES: Country name.

© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


JEPESEN ISTANBUL, TURKIYE
16 SEP 22 30-35
RNAV SID

YESILKÖY
Approach/ Radar (DEP)
131.125
132.050

Apt Elev
325
Trans alt: 12000

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

ASMAP 4E [ASMA4E]
RATVU 4E [RATV4E]
RNAV (GNSS) DEPARTURES
(RWY 36)




JEPPESSEN
ISTANBUL, TURKIYE
16 SEP 22 30-3T
RNAV SID

YES/IKOY	Apt Elev	Trans alt: 12000
Approach/ Radar (DEP)		
131.125	325	
132.050		

1. RADAR required
2. P-RNAV approval required otherwise advise ATC
3. CAUTION: Contact YELIKOV Radar IMMEDIATELY after take-off. At first contact, report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DRR.

DEPARTURE

[ASMA45]
(RWY 36)
EXECUTED WITH LTFJ RNAV (GNSS) STAR RWY 24




© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

VESIKOY Approach/ Radar (DEP)	Apt Elev	Trans alt:
131.125 132.050	325	12000

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact VESIKOY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

BARPE 4F [BARPAF] IVGUS 4F [IVGU4F] RNAV (GNSS) DEPARTURES (RWYS 16L/R)
--



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.

Gnd speed-KT	75	100	150	200	250	300
5.0% V/V (fpm)	380	506	760	1013	1266	1519

SID	ROUTING
BARPE 4F	(900+) - FM047 (K240-; 2100+) - FM056 - FM057 - ORIA - BARPE.
IVGUS 4F	(900+) - FM047 (K240-; 2100+) - FM056 - FM057 - ADMIV - IVGUS.

LTFM/1ST
ISTANBUL


JEPRESEN
16 SEP 22 (30-3V)

ISTANBUL, TURKIYE
RNAV SID

VESIKOY	Apptd/ Radar (DEP)	Appt Elev	Trans alt: 12000
131.125	325		
132.050			

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact VESIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

BARPE 4G [BARP4G]
IVGUS 4G [IVGU4G]
RNAV (GNSS) DEPARTURES
(RWYS 17L/R)




SID	ROUTING
BARPE 4G	(760+) - FM052 (K240-) 1800+ - FM054 - FM056 - FM057 - ORIA - BARPE.
IVGUS 4G	(760+) - FM052 (K240-) 1800+ - FM054 - FM056 - FM057 - ADMIV - IVGUS.

YESTIKOY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESTIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

BARPE 4H [BARPAH]
IVGUS 4H [IVGU4H]
RNAV (GNSS) DEPARTURES
(RWY 18)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.						
Grnd speed-KT	75	100	150	200	250	300
5.0% V/V (ft/min)	380	506	760	1013	1266	1519
Initial climb clearance 8000						
SID	ROUTING					
BARPE 4H	(760+) - FM072 (K240-; 2030+) - FM074 - TIBNU (6000+) - ASGAX - TERPU - INPIK - ADMIV - GUEME - ORJAC - BARPE.					
IVGUS 4H	(760+) - FM072 (K240-; 2030+) - FM074 - TIBNU (6000+) - ASGAX - TERPU - INPIK - ADMIV - IVGUS.					

LTFM/IST
ISTANBUL


JEPRESEN
16 SEP 22 (30-3V2)

ISTANBUL, TURKIYE
RNAV SID

YESILKÖY Approach/ Radar (DEP)	Apt Elev	Trans alt: 12000
131.125 132.050	325	

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

BARPE 4V [BARPAV]
IVGUS 4V [IVGU4V]
RNAV (GNSS) DEPARTURES
(RWY 18)
EXECUTED WITH LTF RNAV (GNSS) STAR RWY 06




CHANGES: Country name.

© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

YESTIKOY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESTIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.


BARPE 4C [BARP4C]
IVGUS 4C [IVGU4C]
RNAV (GNSS) DEPARTURES
(RWYS 34L/R)



CHANGES: Country name.

1. RADAR required.
2. P RNAV approval required otherwise advise ATC.
3. CAUTION: Contact VESIKOY, Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DRR.


7. No Turns Prior to DER



YESTIKOY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESTIKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

BARPE 4E [BARPAE]
IVGUS 4E [IVGU4E]
RNAV (GNSS) DEPARTURES
(RWY 36)



LTFM/IST
ISTANBUL


JEPRESEN
16 SEP 22 (30-3V6)

ISTANBUL, TURKIYE
RNAV SID

YESILKOY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKOY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

IBLAL 4F [IBLALF]
TUDBU 4F [TUDBAF]
VADEN 4F [VADE4F]
RNAV (GNSS) DEPARTURES
(RWYS 16L/R)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.						
Grnd speed-KT	75	100	150	200	250	300
5.0% V/V (fpm)	380	506	760	1013	1266	1519

SID	ROUTING
IBLAL 4F	(900+)-FM047(K240-2100+)-FM048-FM049-FM061(8000+)-FM062-FM063-FM064-FM065-IBLAL.
TUDBU 4F	(900+)-FM047(K240-2100+)-FM048-FM049-FM061(8000+)-FM062-FM063-FM064-FM065-TUDBU.
VADEN 4F	(900+)-FM047(K240-2100+)-FM048-FM049-FM061(8000+)-FM062-FM063-FM064-FM065-VADEN.


CHANGES: Country name.

© JEPRESEN, 2020, 2022. ALL RIGHTS RESERVED.

YESILKÖY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after Take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

IBLAL 4G [IBLA4G]
TUDBU 4G [TUDB4G]
VADEN 4G [VADE4G]
RNAV (GNSS) DEPARTURES
(RWYS 17L/R)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.							
Grnd speed-KT	75	100	150	200	250	300	
5.0% V/V (fpm)	380	506	760	1013	1266	1519	

SID	ROUTING
IBLAL 4G	(760+) - FM052 (K240-; 1800+) - FM060 - REDGI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - IBLAL.
TUDBU 4G	(760+) - FM052 (K240-; 1800+) - FM060 - REDGI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - TUDBU.
VADEN 4G	(760+) - FM052 (K240-; 1800+) - FM060 - REDGI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - FM066 - VADEN.

LTFM/IST
ISTANBUL


JEPESEN
16 SEP 22 (30-3V8)

ISTANBUL, TURKIYE
RNAV SID

YESILKÖY Approach/ Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
---	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

IBLAL 4H [IBLA4H]
TUDBU 4H [TUDB4H]
VADEN 4H [VADE4H]
RNAV (GNSS) DEPARTURES
(RWY 18)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.						
Grnd speed-KT	75	100	150	200	250	300
5.0% V/V (fpm)	380	506	760	1013	1266	1519

SID	ROUTING
IBLAL 4H	(760+) - FM072 (K240 - 2030+) - FM073 - HANCI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - IBLAL.
TUDBU 4H	(760+) - FM072 (K240 - 2030+) - FM073 - HANCI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - TUDBU.
VADEN 4H	(760+) - FM072 (K240 - 2030+) - FM073 - HANCI - FM061 (8000+) - FM062 - FM063 - FM064 - FM065 - VADEN.

CHANGES: Country name.

© JEPESEN, 2020, 2022. ALL RIGHTS RESERVED.


LTFM/1ST
ISTANBUL

JEPRESEN ISTANBUL, TURKIYE
16 SEP 22 (30-3V/9) RNAV SID

YESILKÖY Approach / Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
--	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

IBLAL 4C [IBLALC]
TUDBU 4C [TUDB4C]
VADEN 4C [VADE4C]
RNAV (GNSS) DEPARTURES
(RWYS 34L/R)




LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (30-3W)
ISTANBUL, TURKIYE
RNAV SID

YESILKÖY Approach / Radar (DEP) 131.125 132.050	Apt Elev 325	Trans alt: 12000
--	-----------------	------------------

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION: Contact YESILKÖY Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACFT to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

IBLAL 4D [IBLAD]
TUDBU 4D [TUDBAD]
VADEN 4D [VADE4D]
RNAV (GNSS) DEPARTURES
(RWYS 35L/R)



These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.						
Grnd speed-KT	75	100	150	200	250	300
5.0% V/V (ft/min)	380	506	760	1013	1266	1519

SID	ROUTING
IBLAL 4D	(760+) - FM012 (K240-; 1750+) - FM090 - GOVGU - FM091 - IBLAL.
TUDBU 4D	(760+) - FM012 (K240-; 1750+) - FM090 - GOVGU - UNLIR - TUDBU.
VADEN 4D	(760+) - FM012 (K240-; 1750+) - FM011 - ACCUA - VADEN.

JEPPESSEN ISTANBUL, **TÜRKİYE**
16 SEP 22 **30-3W1** **RNAV SID**

RNAV SID

YESILKOY		
Approach / Radar (DEP)	Apt Elev	Trans alt: 12000
131.125	325	
132.050		

1. RADAR required.
2. P-RNAV approval required otherwise advise ATC.
3. CAUTION - Contact YESLIKOV Radar IMMEDIATELY after take-off. At first contact report only Call Sign and SID Designator. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.
4. Check ATIS for current frequency.
5. The use of a SID designator without a cleared level does not authorize the ACP/T to climb on the SID vertical profile.
6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.
7. No Turns Prior to DER.

VADEN

TUDBU

IBLAL

UNLIR

ACCUA

GOVGU

HITMI

GITVO

QUINTE

FMØ32

MAX 240 KT

2200

6400

3000

3500

090°

270°

62

68

50

51

BULGARIA

TURKYE

3625 M

43.4

17.2

301°

297°

19.3

265°

6.6

302°

286°

13.9

349°

024°

020°

4.9

28.9

18.4

288°

299°

9.1

CONTOUR INTERVALS

4000

2000

1000

TEKIRDAG Intl

Corlu Ataturk Intl

and SID Designer. The aircraft is required to comply with the level and speed restrictions depicted on the procedure.

4. Check ATIS for current frequency.

5. The use of a SID designer without a cleared level does not authorize the ACFT to climb on the SID vertical profile.

6. In the event that pilot assesses a published level or speed restriction cannot be met, must inform ATC as soon as possible.

7. No Turns Prior to DER.

IBLAL 4E [IBLA4E]

TUDBU 4E [TUDB4E]

VADEN 4E [VADE4E]

RNAV (GNSS) DEPARTURES

(RWY 36)

These SIDs require a minimum climb gradient of 5.0% (304 per NM) up to 8000.

Grid speed-KT	75	100	150	200	250	300
5.0% V/V (fpm)	380	506	760	1013	1266	1519

Initial climb clearance 8000	
SID	ROUTING
IBAL 4E	(760+)- FMS32 (K240- 2200+)- QUNITE (6400+)- GITVO - HITMI - IBAL.
TUDBU 4E	(760+)- FMS32 (K240- 2200+)- QUNITE (6400+)- GITVO - GOVGU - UNLIR - TUDBU.
VADEN 4E	(760+)- FMS32 (K240- 2200+)- QUNITE (6400+)- GITVO - GOVGU - ACCUA - VADEN.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.


YESILKOY
Approach/
Radar (DEP)
131.125
132.050

Apt Elev
325

Trans alt: 12000

1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. CAUTION: At first contact report only Call Sign and SID Designator.
3. CAUTION: This SID is only available for the aircraft unable to comply the P-RNAV departure procedures.
4. CAUTION: The aircraft executing this SID may lose departure sequence and be subject to a delay.

IST 1F DEPARTURE
(RWYS 16L/R)



This SID requires a minimum climb gradient of 322 per NM (5.3%) up to 8000.

Gnd speed-KT	75	100	150	200	250	300
322 per NM	402	537	805	1073	1342	1610

Initial climb clearance **8000**


ROUTING

Proceed to OGIBI on UHL R174, then turn LEFT and proceed to IST VOR on IST R306. After IST VOR follow flight plan.

Trans alt: 12000

1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. CAUTION: At first contact report only Call Sign and SID Designator.
3. CAUTION: This SID is only available for the aircraft unable to comply the P-RNAV departure procedures.
4. CAUTION: The aircraft executing this SID may lose departure sequence and be subject to a delay.

25




ROUTING

Proceed to GAPDI on UHM R174, then turn LEFT and proceed to IST VOR on IST R313. After IST VOR follow flight plan.

YESILKOY
Approach/
Radar (DEP)
131.125
132.050Apt Elev
325

Trans alt: 12000
1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. CAUTION: At first contact report only Call Sign and SID Designator.
3. CAUTION: This SID is only available for the aircraft unable to comply the P-RNAV departure procedures.
4. CAUTION: The aircraft executing this SID may lose departure sequence and be subject to a delay.

IST 1H DEPARTURE
(RWY 18)

Initial climb clearance 8000


ROUTING

Proceed to DIKIZ on UHN R174, then turn LEFT and proceed to IST VOR on IST R341. After IST VOR follow flight plan.

Trans alt: 12000

1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. CAUTION: At first contact report only Call Sign and SID Designator.
3. CAUTION: This SID is only available for the aircraft unable to comply the P-RNAV departure procedures.
4. CAUTION: The aircraft executing this SID may lose departure sequence and be subject to a delay.

Month	Number of Visitors
January	10
February	15
March	20
April	25
May	30
June	35
July	40
August	45
September	30
October	20
November	15
December	10




SQUAWK 7600. Continue climb 10000.
 MAINTAIN 10000 for 3 minutes, then
 climb to the filed level. After IST VOR
 follow the flight plan. If available call
 telephone number 0090 212 465 01 21.

ROUTING


Proceed to NEDBA on UHL R354. Cross NEDBA at or above 3000, then turn LEFT and proceed on CEK R004 (184° bearing to CEK NDB), at D15.0 CEK turn LEFT, proceed to IST VOR on IST R324. After IST VOR follow the flight plan.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.



YESILKOY
Approach/
Radar (DEP)
131.125
132.050Apt Elev
325

Trans alt: 12000
1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. CAUTION: At first contact report only Call Sign and SID Designator.
3. CAUTION: This SID is only available for the aircraft unable to comply the P-RNAV departure procedures.
4. CAUTION: The aircraft executing this SID may lose departure sequence and be subject to a delay.

IST 1E DEPARTURE
(RWY 36)

This SID requires a minimum climb gradient of 322 per NM (5.3%) up to 8000.

Gnd speed-KT	75	100	150	200	250	300
322 per NM	402	537	805	1073	1342	1610

LOST COMMS

Squawk 7600. Continue climb 10000. MAINTAIN 10000 for 3 minutes, then climb to the filed level. After IST VOR follow the flight plan. If available call telephone number 0090 212 465 01 21.

LOST COMMS


Initial climb clearance 8000

ROUTING

Proceed to ISSIZ on UHN R354. Cross ISSIZ at or above 3000, then turn RIGHT and proceed to IST VOR on IST R359. After IST VOR follow the flight plan.

YESILKOY
Approach/
Radar (DEP)
131.125
132.050Apt Elev
325


Trans alt: 12000
1. Contact YESILKOY Radar IMMEDIATELY after take-off.
2. At first contact report only Call Sign and SID Designator.
3. CAUTION: These SIDs are only available for the aircraft destined to LTBA or LTFJ.
4. CAUTION: At or before IST VOR, the aircraft will be cleared or RADAR vectored to a point or final track, where the relevant approach can be made.

IST 1N DEPARTURE
(RWYS 35L/R)IST 1P DEPARTURE
(RWYS 17L/R)

Initial climb clearance 5000

SID	RWY	ROUTING
IST 1N	35L/R	Proceed to LADUX on UHM R354, cross LADUX at or above 3000, then turn LEFT and proceed on CEK R004 (184° bearing to CEK NDB), at D15.0 CEK turn LEFT, proceed to IST VOR on IST R324.
IST 1P	17L/R	Proceed to GAPDI on UHM R174, then turn LEFT and proceed to IST VOR on IST R313.

For AIRPORT BRIEFING refer to 30-1P pages.
See 30-9H for taxi speed restrictions.



(For information only, not to be construed as ATC instructions.)

- | ADDITIONAL RUNWAY INFORMATION | | | | | | | | | | USABLE LENGTHS | | | | |
|-------------------------------|--|-----------------|------------|-------------------------|--|--------------------|--|--|--|-----------------|-------------|----------|-------|------|
| | | | | | | | | | | LANDING BEYOND | | TAKE-OFF | WIDTH | |
| | | | | | | | | | | Threshold | Glide Slope | | | |
| RWY 16L | HIRL (60m) HIALS REIL PAPI (3.0°) | 1 | RVR | | | | | | | | | | | 148' |
| 34R | HIRL (60m) HIALS REIL PAPI (3.0°) | 2 | RVR | | | | | | | | | | | 45m |
| 1 | HSTII: A6B | 2 | HSTII: A8B | | | | | | | | | | | |
| 3 TAKE-OFF RUN AVAILABLE | | | | | | | | | | | | | | |
| RWY 16L: | | | | | | | | | | | | | | |
| From rwy head | | | | | | | | | | | | | | |
| | | 12,303' (3750m) | | | | 12,303' (3750m) | | | | 12,303' (3750m) | | | | |
| 1wy A1/A, A1/B int | | 11,998' (3653m) | | | | 1wy A2/A, A2/B int | | | | 11,982' (3653m) | | | | |
| 1wy A10/A, A10/B int | | 11,594' (3543m) | | | | 1wy A3/A, A3/B int | | | | 11,624' (3543m) | | | | |
| 1wy A9/B int | | 10,033' (3058m) | | | | 1wy A4 int | | | | 11,306' (3446m) | | | | |
| 1wy A/B int | | 7335' (2248m) | | | | 1wy A/B int | | | | 8885' (2708m) | | | | |
| 16R | HIRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) | 2 | RVR | | | | | | | 11,432' (3491m) | | | | 197' |
| 34L | HIRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) | 2 | RVR | | | | | | | 11,088' (3380m) | | | | 6m |
| 1 | HSTI: A3A | HSTII: A5A, A6A | 3 | HSTII: A7A, A8A, A9A | | | | | | | | | | |
| 3 TAKE-OFF RUN AVAILABLE | | | | | | | | | | | | | | |
| RWY 16R: | | | | | | | | | | | | | | |
| From rwy head | | | | | | | | | | | | | | |
| | | 12,303' (3750m) | | | | 12,303' (3750m) | | | | 12,303' (3750m) | | | | |
| 1wy A1/A int | | 11,998' (3653m) | | | | 1wy A2/A int | | | | 11,985' (3653m) | | | | |
| 1wy A11/A int | | 11,594' (3543m) | | | | 1wy A3/A int | | | | 11,624' (3543m) | | | | |
| 1wy A10/A int | | 11,594' (3543m) | | | | 1wy A4 int | | | | | | | | |
| 17L | HIRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) | 2 | RVR | | | | | | | 12,540' 3822m | | | | 197' |
| 35R | HIRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) | 2 | RVR | | | | | | | 12,236' 3730m | | | | 60m |
| 1 | HSTI: C6A | HSTII: C6, C7 | 3 | HSTII: B8B, C8, C9, C10 | | | | | | | | | | |
| 3 TAKE-OFF RUN AVAILABLE | | | | | | | | | | | | | | |
| RWY 17L: | | | | | | | | | | | | | | |
| From rwy head | | | | | | | | | | | | | | |
| | | 13,451' (4100m) | | | | 13,451' (4100m) | | | | 13,451' (4100m) | | | | |
| 1wy C13 int | | 13,136' (4004m) | | | | 1wy C2A int | | | | 13,136' (4004m) | | | | |
| 1wy C12 int | | 12,818' (3907m) | | | | 1wy C3A int | | | | 12,818' (3907m) | | | | |
| 1wy B9B/C11 int | | 12,034' (3668m) | | | | 1wy B3B/C4A int | | | | 12,067' (3678m) | | | | |
| | | | | | | 1wy B4B/C5A int | | | | 11,624' (3543m) | | | | |
| | | | | | | 1wy B5B int | | | | 9508' (2898m) | | | | |
| 17R | HIRL (60m) HIALS REIL PAPI (3.0°) | 10 | RVR | | | | | | | | | | | 148' |
| 35L | HIRL (60m) HIALS REIL PAPI (3.0°) | 11 | RVR | | | | | | | | | | | 45m |
| 1 | HSTII: B6 | 1 | HSTII: B7 | | | | | | | | | | | |
| 3 TAKE-OFF RUN AVAILABLE | | | | | | | | | | | | | | |
| RWY 17R: | | | | | | | | | | | | | | |
| From rwy head | | | | | | | | | | | | | | |
| | | 13,451' (4100m) | | | | 13,451' (4100m) | | | | 13,451' (4100m) | | | | |
| 1wy B11 int | | 13,136' (4004m) | | | | 1wy B2 int | | | | 13,136' (4004m) | | | | |
| 1wy B10 int | | 12,746' (3885m) | | | | 1wy B3A/B3B int | | | | 12,067' (3678m) | | | | |
| 1wy B9A/B9B int | | 12,034' (3668m) | | | | 1wy B4A/B4B int | | | | 11,624' (3543m) | | | | |
| 1wy B8A int | | 8524' (2598m) | | | | 1wy B5A/B5B int | | | | | | | | |

HOT SPOTS

(For information only, not to be construed as ATC instructions.)

- HS1** Landing ACFT on RWY 16R/34L will cross RWY 16L/34R only when TWR gives permission to cross the RWY and the Red Stop Bar lights are switched off.
- HS2** Unless otherwise specified by ATC unit, landing ACFT on RWY 17L/35R shall not vacate the RWY via B5B or B8B.
- HS4** ACFT taxiing into or pushing out from ACFT parking stands B2, B4, C1, C2, C3, C4, D1, D3 and D5 shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY centerline. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS5** ACFT taxiing into or pushing out from ACFT parking stands D2, D4, E1, E2, E3, E4, F2, F4, F4L and FAR shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY centerline. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS6** ACFT taxiing into or pushing out from ACFT parking stands B6R and B8L shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY T3. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS7** ACFT taxiing into or pushing out from ACFT parking stands F6L and F8R shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY T9. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS8** ACFT taxiing into or pushing out from ACFT parking stands A2L, A2, B1 and B1R shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY T2. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS9** ACFT taxiing into or pushing out from ACFT parking stands F1L, F1, G2 and G2R shall observe other ACFT in the adjacent parking stands because ACFT parking stand lead in lines are converging towards TWY T11. There is a risk of collision with adjacent ACFT while two ACFT are taxiing in at the same time, or one is taxiing in and other one is taxiing out or vice versa or ACFT are taxiing out at the same time.
- HS10** Simultaneous taxiing in or pushing out from ACFT parking stands 214 and 220 are not allowed due to risk of collision.
- HS11** Taxiing ACFT on T1 towards North shall stop at TULIP (N41 15.9 E028 44.0) and request further ATC instructions. ACFT taxiing on TWY T1 towards North beyond TULIP is under risk of collision with ACFT taxiing on TWY E.
- HS12** Taxiing ACFT on T12 towards North shall stop at ROSE (N41 15.9 E028 45.1) and request further ATC instructions. ACFT taxiing on TWY T12 towards North beyond ROSE is under risk of collision with ACFT taxiing on TWY F.
- HS13** While Code E or Code F ACFT is holding short for RWY 35L at TWY B1A and TWY B2, no other Code E or Code F category ACFT is allowed to taxi on TWY B.
- HS14** Code E ACFT taxiing on TWY TC and TWY TD shall not stop once taxiing. In case Code E ACFT stops on TWY TC and TWY TD after start of taxiing, ACFT shall not attempt to taxi again. The pilot shall request towing until a safe point before continuing taxiing due to very high jet blast effect of Code E ACFT.
- HS15** For RWY 18 Southern operations, there is a risk of collision between the landing ACFT vacating RWY via TWY G10 and TWY G9A and ACFT taxiing via TWY G, TWY G9, TWY NE and TWY N1.


ADDITIONAL RUNWAY INFORMATION

USABLE LENGTHS

RWY		—LANDING BEYOND—		TAKE-OFF	WIDTH
		Threshold	Glide Slope		
16L	HRL (60m) HIALS REIL PAPI (3.0°) ①	RVR		③	148' 45m
34R	HRL (60m) HIALS REIL PAPI (3.0°) ②	RVR			
① HSTL: A6B ② HSTL: A8B					
③ TAKE-OFF RUN AVAILABLE					
RWY 16L:					
From rwy head	12,303' (3750m)	From rwy head	12,303' (3750m)		
twy A1/A1B int	11,985' (3653m)	twy A2/A1B28 int	11,985' (3653m)		
twy A10A/A10B int	11,594' (3534m)	twy A3/A1A38 int	11,624' (3543m)		
twy A08 int	10,033' (3058m)	twy A4 int	11,306' (3446m)		
twy A07 int	7375' (2248m)	twy A5B int	8885' (2708m)		
16R	HRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) ① RVR		11,452' 3491m	⑥	197' 60m
34L	HRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) ② RVR		11,088' 3380m		
① HST: A5A HSTL: A5A, A6A ② HSTL: A7A, A8A, A9A					
③ TAKE-OFF RUN AVAILABLE					
RWY 16R:					
From rwy head	12,303' (3750m)	From rwy head	12,303' (3750m)		
twy A11A int	11,985' (3653m)	twy A2A int	11,985' (3653m)		
twy A10A int	11,594' (3534m)	twy A3A int	11,624' (3543m)		
17L	HRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) ② RVR		12,540' 3822m	③	197' 60m
35R	HRL (60m) CL (15m) ALSF-II TDZ REIL PAPI (3.0°) ③ RVR		12,236' 3730m		
② HST: C5A HSTL: C6, C7 ③ HSTL: B8B, C8, C9, C10					
③ TAKE-OFF RUN AVAILABLE					
RWY 17L:					
From rwy head	13,451' (4100m)	From rwy head	13,451' (4100m)		
twy C13 int	13,136' (4004m)	twy C2A int	13,136' (4004m)		
twy C12 int	12,818' (3907m)	twy C3A int	12,818' (3907m)		
twy B9B/C11 int	12,034' (3668m)	twy B3B/C4A int	12,067' (3678m)		
		twy B4B/C5A int	11,624' (3543m)		
		twy B5B int	9508' (2898m)		
17R	HRL (60m) HIALS REIL PAPI (3.0°) ① RVR			④	148' 45m
35L	HRL (60m) HIALS REIL PAPI (3.0°) ②	RVR			
① HSTL: B6 ② HSTL: B7					
③ TAKE-OFF RUN AVAILABLE					
RWY 17R:					
From rwy head	13,451' (4100m)	From rwy head	13,451' (4100m)		
twy B11 int	13,136' (4004m)	twy B2 int	13,136' (4004m)		
twy B10 int	12,746' (3885m)	twy B3A/B3B int	12,067' (3678m)		
twy B9A/B9B int	12,034' (3668m)	twy B4A/B4B int	11,624' (3543m)		
twy B8A int	8524' (2598m)	twy B5A/B5B int	9508' (2898m)		
18	HRL ③ CL ④ HIALS-II TDZ REIL PAPI-L (3.0°) ⑤ RVR		9128' 2782m	⑤	148' 45m
36	HRL ③ CL ④ HIALS-II TDZ REIL PAPI-L (3.0°) ⑥ RVR		8885' 2708m		
③ spacing 15m. ④ HSTL: H2, H3, G9A, G10 ⑤ HSTL: H6, H7, G13, G14					
⑥ TAKE-OFF RUN AVAILABLE					
RWY 18:					
From rwy head	10,040' (3060m)	From rwy head	10,040' (3060m)		
twy G16 int	9744' (2970m)	twy G7A int	9724' (2964m)		
twy G15 int	9446' (2879m)	twy G8A int	9403' (2866m)		
Std/State	Low Visibility Take-off	TAKE-OFF			
①	HRL & CL (spacing 15m or less) & relevant RVR	RL & CL & relevant RVR	RL & CL	RL or CL	Adequate Vis Ref
TDZ R125m	TDZ R150m	R200m	R300m	R/V400m	R/V500m
Mid R125m	Mid R150m				
Rollout R125m	Rollout R150m				
① RWY 16R, 17L, 18, 34L, 35R, 36: R75m with approved lateral guidance system or HUD/HUDIS.					

CHANGES: Country name.


© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.





STAND No.		COORDINATES		INS COORDINATES			STAND No.		COORDINATES		STAND No.		COORDINATES		
APRON 1															
100 thru 102	N41 16.5	E028 44.0	316L thru 317	N41 15.1	E028 45.1	B16	N41 16.0	E028 44.2	G6L thru G6R	N41 15.6	E028 45.0				
103 thru 105	N41 16.5	E028 44.1	317R	N41 15.0	E028 45.1	B17	N41 16.1	E028 44.2	G7L thru G6R	N41 15.5	E028 45.0				
106 thru 108	N41 16.5	E028 44.2	318L thru 318R	N41 15.1	E028 45.2	B18L	N41 16.0	E028 44.3	G9L thru G9R	N41 15.4	E028 45.0				
109	N41 16.5	E028 44.3	319L	N41 15.0	E028 45.2	B18, B18R	N41 16.0	E028 44.2	G10L	N41 15.4	E028 44.9				
110 thru 112	N41 16.5	E028 44.4	319, 319R	N41 15.1	E028 45.2	C1 thru C3	N41 15.8	E028 44.4	G10, G10R	N41 15.4	E028 45.0				
APRON 2															
113 thru 115	N41 16.5	E028 44.5	APRON 4												
116 thru 119	N41 16.5	E028 44.6	401	N41 17.6	E028 42.8	D1	N41 15.8	E028 44.5	G11L thru G11R			N41 15.4	E028 44.9		
120, 121	N41 16.5	E028 44.7	402, 403	N41 17.6	E028 42.9	D2	N41 15.8	E028 44.6	DEICING 1 APRON						
122	N41 16.5	E028 44.8	404	N41 17.6	E028 43.0	D3	N41 15.8	E028 44.5	H10L thru H10R	N41 17.7	E028 42.8				
123 thru 126	N41 16.5	E028 44.9	405L	N41 17.6	E028 43.0	D4	N41 15.8	E028 44.6	H11L thru H11R	N41 17.7	E028 42.9				
127 thru 129	N41 16.5	E028 45.0	405, 405R	N41 17.6	E028 43.0	D5	N41 15.9	E028 44.5	H12L thru H12R	N41 17.7	E028 43.0				
130, 131	N41 16.5	E028 45.1	406, 407	N41 17.6	E028 43.1	D6	N41 15.9	E028 44.6	H13L, H13	N41 17.7	E028 43.1				
132 thru 133R	N41 16.5	E028 44.0	408, 409	N41 17.6	E028 43.2	D7	N41 15.9	E028 44.5	H13R	N41 17.7	E028 43.0				
134L thru 135L	N41 16.5	E028 44.1	APRON 5												
135 thru 136R	N41 16.5	E028 44.2	DEICING 2 APRON												
137L thru 137R	N41 16.5	E028 44.3	501	N41 17.2	E028 42.8	D10	N41 16.0	E028 44.6	H14L thru H14R	N41 17.7	E028 43.1				
138L thru 139	N41 16.5	E028 44.4	502, 503	N41 17.2	E028 42.9	D11	N41 16.0	E028 44.5	DEICING 3 APRON						
139R thru 140R	N41 16.5	E028 44.5	504, 505	N41 17.2	E028 43.0	D12	N41 16.0	E028 44.6	H20L thru H20R	N41 16.0	E028 42.8				
141L thru 142R	N41 16.5	E028 44.6	506	N41 17.2	E028 43.1	D13	N41 16.0	E028 44.5	H21L thru H22L	N41 16.0	E028 42.9				
143L thru 143R	N41 16.5	E028 44.7	507, 508	N41 17.2	E028 43.2	D14	N41 16.0	E028 44.6	H22 thru H23	N41 16.0	E028 43.0				
144L thru 144R	N41 16.5	E028 44.8	509	N41 17.2	E028 43.3	D15	N41 16.0	E028 44.5	H23R thru H24R	N41 16.0	E028 43.1				
145L thru 146R	N41 16.5	E028 44.9	TERMINAL CONTACT APRON												
147L thru 148	N41 16.5	E028 45.0	DEICING 4 APRON												
148R, 149	N41 16.5	E028 45.1	DEICING 5 APRON												
APRON 3															
200 thru 203	N41 15.3	E028 44.2	A2L thru A3L	N41 15.7	E028 44.2	E2 thru E4	N41 15.8	E028 44.7	H30L thru H30R	N41 16.3	E028 44.0				
204 thru 207	N41 15.2	E028 44.2	A3, A3R	N41 15.6	E028 44.2	F1L thru F1R	N41 15.8	E028 44.9	H31L thru H32L	N41 16.3	E028 44.1				
208 thru 211	N41 15.1	E028 44.2	A5L	N41 15.6	E028 44.1	F2	N41 15.9	E028 44.8	H32 thru H33	N41 16.3	E028 44.2				
212 thru 214	N41 15.0	E028 44.2	A5, A5R	N41 15.6	E028 44.2	F3L thru F3R	N41 15.8	E028 44.8	H33R	N41 16.3	E028 44.3				
215L thru 215R	N41 15.3	E028 44.0	A6L	N41 15.6	E028 44.1	F4L	N41 15.9	E028 44.8	H35L thru H35R	N41 16.3	E028 44.4				
216L	N41 15.2	E028 44.0	A6 thru A8L	N41 15.5	E028 44.1	F4, FAR	N41 15.8	E028 44.8	H36L thru H36R	N41 16.3	E028 44.5				
216, 216R	N41 15.3	E028 44.0	A8 thru A9	N41 15.4	E028 44.1	F5L	N41 15.8	E028 45.0	DEICING 5 APRON						
217L thru 217R	N41 15.2	E028 44.0	A10L thru A11	N41 15.4	E028 44.2	F5, F5R	N41 15.9	E028 44.9	H50L thru H51	N41 15.3	E028 45.7				
218L	N41 15.1	E028 43.9	A11R	N41 15.4	E028 44.3	F6L thru F6R	N41 15.9	E028 44.8							
218, 218R	N41 15.1	E028 44.0	B1L	N41 15.8	E028 44.2	F7L thru F7R	N41 15.9	E028 45.0							
219L	N41 15.1	E028 43.9	B1, B1R	N41 15.7	E028 44.2	F8L	N41 15.9	E028 44.8							
219, 219R	N41 15.0	E028 44.0	B2	N41 15.8	E028 44.3	F8, F8R	N41 15.9	E028 44.9							
220L thru 221R	N41 14.9	E028 44.1	B3L thru B3R	N41 15.8	E028 44.2	F9L	N41 15.9	E028 45.0							
222L thru 223	N41 14.9	E028 44.0	B4	N41 15.8	E028 44.3	F9, F9R	N41 16.0	E028 45.0							
223R thru 224R	N41 14.9	E028 43.9	B5L	N41 15.8	E028 44.1	F12L	N41 16.0	E028 44.8							
225	N41 15.1	E028 44.0	B5, B5R	N41 15.8	E028 44.2	F12, F12R	N41 16.0	E028 44.9							
226	N41 15.0	E028 44.0	B6L, B6	N41 15.9	E028 44.3	F13L thru F13R	N41 16.0	E028 45.0							
APRON 5															
300 thru 302	N41 15.3	E028 44.9	B6R	N41 15.9	E028 44.2	F14	N41 16.0	E028 44.9							
303 thru 307	N41 15.2	E028 44.9	B7L thru B7R	N41 15.9	E028 44.1	F15	N41 16.0	E028 44.8							
308 thru 311	N41 15.1	E028 44.9	B8L	N41 15.9	E028 44.3	F16, F17	N41 16.1	E028 44.9							
312	N41 15.0	E028 44.9	B8, B8R	N41 15.9	E028 44.2	F18	N41 16.1	E028 45.0							
313L thru 314R	N41 15.3	E028 45.1	B9L thru B9R	N41 15.9	E028 44.1	F19	N41 16.0	E028 45.0							
315L thru 315R	N41 15.2	E028 45.1	B10L	N41 16.0	E028 44.3	G2L thru G4R	N41 15.7	E028 44.9							
			B10, B10R	N41 16.0	E028 44.2	G5L	N41 15.6	E028 45.0							
			B12L thru B15	N41 16.0	E028 44.1	G5, G5R	N41 15.6	E028 44.9							

CHANGES: Country name, APRON 4 & APRON 5 stands moved from 30-9E, CARGO 1 thru 5 APRONS stands moved to 30-9E.

INS COORDINATES		
STAND No.	COORDINATES	
CARGO 1 THRU 5 APRONS		
K1L thru K1R	N41 16.1	E028 42.8
K2L thru K3R	N41 16.1	E028 42.9
K4L thru K5	N41 16.1	E028 43.0
K5R thru K6R	N41 16.1	E028 43.1
K7L thru K8R	N41 16.1	E028 43.2
K9L thru K9R	N41 16.1	E028 43.3
K10, K11	N41 16.2	E028 43.2
K12, K13	N41 16.3	E028 43.2
K14, K15	N41 16.4	E028 43.2
K16 thru K18	N41 16.5	E028 43.2
K19	N41 16.6	E028 43.2
K20, K21	N41 16.7	E028 43.2
K50, K51	N41 16.7	E028 42.8
K52, K53	N41 16.6	E028 42.8
K54, K55	N41 16.3	E028 42.8
K56, K57	N41 16.2	E028 42.8









TAXI ROUTES ARRIVAL RWYS 17L, 35R (CONTD 2)


STANDARD TAXI ROUTES
For RWY 17L/35R:
ARR 2E: Arrival traffic vacating RWY 17L/35R,
shall use TWYs C, N5, T9, N3 and F and hold
position at clearance limit given by ATC.








CHANGES: Country name, Hot Spots HS1, HS2, HS3 and HS15 depiction.


© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.














CHANGES: Speed limit MAX 10 KT with taxi.


© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
28 OCT 22 (50-9G1) EET 3 NOV
JEPPESEN
ISTANBUL, TURKIYE
ISTANBUL












CHANGES: Taxi route DEP 2D added; taxi routes RWY 35R moved to 30-9G-6.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.







PUSHBACK PROCEDURES**1. INTRODUCTION**

- 1.1. The purpose of these pages is to inform all external and internal stakeholders of Istanbul Airport about the pushback procedures of all ACFT stands.
- 1.2. The objective of the pushback procedures is to reduce ground conflicts, delays and radiotelephony congestion thereby enhancing the operational efficiency and safety of Istanbul Airport.
- 1.3. All stands at Istanbul Airport have standard prescribed pushback procedures.
- 1.4. On some occasions due to the ground traffic situation, obstacles or work in progress, a non-standard pushback is required. In these situations, a non-standard pushback instruction will be issued to the pilot by ATC. ATC instructions overrule the standard procedures.

2. PROCEDURES

- 2.1. Pilots shall switch on their transponders before the time of the request for pushback. ACFT not identified on the ATC system will not allowed for pushback.
- 2.2. If there is any uncertainty or possibility of misunderstanding, pushbacks shall never be commenced, pushback operators shall contact the flight deck and request a conformation of the instruction by ATC.
- 2.3. If ATC may thought that the instruction is not completely understood by the flight crew or possibility of commencing wrong pushback, ATC may give an estimated pushback time in order to regulate traffic.
- 2.4. Unless prior permission has been obtained from the Airside Operation, pushback is compulsory at all stands. It is forbidden to execute power back through using engine's reverse thrust.
- 2.5. Pushback shall start within at the least 1 minute after approval has been received from Ground, taking into account the traffic information and/or restrictions contained in the approval message otherwise ATC may give an estimated start time.
- 2.6. The ground crew is responsible for ensuring that the area in the front, behind and around the ACFT is clear of personnel, vehicles, equipment and other obstructions before commencing pushback.
- 2.7. Portion of TWY T3 from intersection TWY NW towards South until the end of TWY T3, portion of TWY T5 from intersection TWY NW towards South until the end of TWY T5, portion of TWY T7 from intersection TWY NE towards South until the end of TWY T7 and portion of TWY T9 from intersection TWY NE towards South until the end of TWY T9 are defined as LOW POWER ZONE.
- 2.8. Code D and Code E arrival ACFT taxiing on T3 TWY in the LOW POWER ZONE, shall turn to parking stands D9, D11, D13, D15, D17 and D19 via TC TWY at a lower power rate.
- 2.9. Code D and Code E arrival ACFT taxiing on T9 TWY in the LOW POWER ZONE, shall turn to parking stands D8, D10, D12, D14, D16 and D20 via TD TWY at a lower power rate.
- 2.10. E2, F2, N6, T1, T4, T8, T12 and North of G2A TWYs are Code C (max wingspan 118'/36m) designated TWYs, these TWYs are not available for Code D, Code E and Code F ACFT.
- 2.11. In case ACFT need to start up one engine or both engines at parking stand, ATC shall accept the request after obtaining safety report from Airside Operation. ACFT shall start up engines with minimum power (on idle power) when parking at stand or during pushback.

3. CROSS BLEED START PROCEDURES

- 3.1. In case an ACFT needs to run the engines with a higher power than the idle power, such as "Cross Bleed Start", pilot shall notify ATC of this request before pushback. Engines may only be run at more than the minimum power at the taxi center line. If such an operation is requested, the ACFT may have a delay depending on the ground traffic.
- 3.2. Code D and Code E ACFT that requires Cross-bleed engine start from parking positions B4, B6 and B8 shall pushback to PSN1, Code D and Code E ACFT that requires Cross-bleed engine start from parking positions F4, F6 and F8 shall pushback to PSN3 facing South and start engines on these positions.
- 3.3. Code D and Code E ACFT that requires Cross-bleed engine start in the Cul-de-Sac areas shall start their engines at the North side of TC and TD TWYs. Code D and Code E ACFT shall not start cross-bleed at PSN2 and PSN4 points, Code C ACFT can start cross-bleed at PSN2 and PSN4 points.
- 3.4. Pilots of ACFT that require "Cross-bleed Start" will notify ATC of their request as shown at item 4.3.

PUSHBACK PROCEDURES (CONTD 1)

4. PHRASEOLOGY

- 4.1. To approve the pushback and start up request from pilot, basic phraseology used by ATC maybe as given below:
"ATC: [Call sign of ACFT] GROUND, PUSHBACK AND START UP APPROVED RUNWAY--, FACE --".
- 4.2. To approve the pushback and startup request from pilot, phraseology used by ATC for defined PSN points maybe as given below:
"ATC: [Call sign of ACFT] GROUND, PUSHBACK AND START UP APPROVED RUNWAY--, PSN--".
- 4.3. Flight crews intending to 'Cross Bleed Start' shall advise ATC before pushback as;
"GROUND [Call sign of ACFT] + [Parking Position] + REQUEST CROSS BLEED START".
- 4.4. The direction information in a standard pushback phraseology indicates the final direction of the ACFT after pushback is completed.
- 4.5. ATC instructions may include a condition to be complied with. For example:
"AFTER B737 PASSING BEHIND, PUSHBACK APPROVED".
- 4.6. If any doubt exists as to which ACFT is the 'subject ACFT' of a conditional clearance, the ground crew shall ask the flight crew to confirm with ATC.
- 4.7. ATC may give long pushback, pull forward or additional instructions to increase separation, clear a stand or a TWY or point out the first TWY of the departure ACFT.
Example 1: "PUSHBACK AND START UP APPROVED RWY 36 FACE SOUTH, LONG PUSHBACK ABEAM STAND F6".
Example 2: "PUSHBACK AND START UP APPROVED RWY 36 FACE SOUTH, AFTER PUSHBACK PULL FORWARD ABEAM STAND F6".
Example 3: "PUSHBACK AND START UP APPROVED RWY 36 FACE SOUTH, KEEP CLEAR TWY F6".
Example 4: "PUSHBACK AND START UP APPROVED RWY 36 FACE SOUTH, EXPECT TAXI VIA TWY F6".
Note: In these phraseologies 'ABEAM' means the nearest TWY centerline to the subject parking stand.

5. HOT SPOTS

See 30-9A for description of Hot Spots.

6. TOWING

- 6.1. Ground crews who operate towing in Istanbul Airport must be appropriately trained in APT layout and radiotelephony.
- 6.2. Towing is not permitted unless under a leader escort from Airside Operation. The tow crew shall wait until the leader vehicle has arrived before pushback clearance is requested.
- 6.3. Tow crews shall give full readbacks to ATC instructions. Additional care should be taken when tow crews are subject to a conditional clearance. It is vital that the correct ACFT or vehicle specified in the condition is identified. If there is any doubt, tow crews shall ask clarification from ATC.
- 6.4. Towing crew is responsible to maintain and listen carefully the relevant Ground frequency until the towing process is completed.
- 6.5. An illuminated red stop bar means STOP. Tow crews shall not put any part of the ACFT beyond the stop bar until it is extinguished, and ATC permission has been received.
- 6.6. Tow crews shall inform ATC if they are unable to execute an instruction or face difficulty in executing an instruction.

7. STANDARD TRAFFIC FLOW OF TERMINAL CONTACT APRON AREA

Standard taxi route is counterclockwise at West Cul-de-Sac while clockwise at East Cul-de-Sac.

PUSHBACK PROCEDURES (CONTD 2)
TERMINAL CONTACT APRON - Southwest area

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
A2L thru A2R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North and continue push until TWY E8 will remain clear of ACFT.	HS8 (Be aware of the ACFT pushbacks from stands A2L, A2, B1 and B1R).	Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South and continue push until TWY E8 will remain clear of ACFT.		Pushback Approved Face South
A3L thru A7R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South.		Pushback Approved Face South
A8L thru A8R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North. TWY E5 will remain clear of ACFT.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South.		Pushback Approved Face South
A9	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South.		Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North, then pulled forward until TWY E5 will remain clear of ACFT.		Pushback Approved Face North
A10 A11	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY E3 to face North until its nosewheel is at the PSN5 point.	E2 TWY is CAT C.	Pushback Approved PSN5
A10L, A10R A11L, A11R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY E3 to face North until its nosewheel is at the PSN5 point.		Pushback Approved PSN5
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face North and continue push until TWY T2 will remain clear of ACFT.		Pushback Approved Face South on E2 TWY

TERMINAL CONTACT APRON - Northwest area

B1L thru B1R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South until TWY E8 will remain clear of ACFT.	HS8 (Be aware of the ACFT pushbacks from stands A2L, A2, B1 and B1R).	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North and continue push until TWY E8 will remain clear of ACFT.		Pushback Approved Face North
B3L thru B3R B5L thru B5R B7L thru B7R B9L thru B9R B12L thru B12R B13	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face South.		Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T2 to face North.		Pushback Approved Face North

PUSHBACK PROCEDURES (CONTD 3)			
STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
B14 B15 B16	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY NW to face West.	The ACFT pushing back from stand B14 facing East should pull forward until T2 TWY is clear.	Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY NW to face East.		Pushback Approved Face East
TERMINAL CONTACT APRON - West Cul-de-Sac area			
B10L thru B10R B17 B18L thru B18R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing South. Taxi out via TC TWY.	The ACFT pushing back from stand B17 should pull forward until NW TWY is clear. CAT D and E ACFTs pushing back face South shall use TWY TC.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing North.		Pushback Approved Face North
D13 D15 D17	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing North.	CAT D and E ACFTs pushing back face South shall use TWY TC.	Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing South.		Pushback Approved Face South
D19	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY NW facing East and continue push until TWY T3 will remain clear of ACFT.		Pushback Approved Face East on NW TWY
B4	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing South and continue push until its nosewheel is at the PSN1 point. Taxi out via TC TWY.	HS4 (Be aware of the ACFT pushbacks from stands B2, B4, C1, C2, C3, C4, D1, D3 and D5).	Pushback Approved PSN1
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing South, then pulled forward until its nosewheel is at the PSN2 point on TWY T5 facing North.		Pushback Approved PSN2
B6L thru B6R B8L thru B8R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing South and continue push until its nosewheel is at the PSN1 point. Taxi out via TC TWY.	HS6 (Be aware of the ACFT pushbacks from stands B6R and B8L). CAT D and E ACFTs pushing back face South shall use TWY TC.	Pushback Approved PSN1
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing North abeam stand B6, TWY TC will remain clear of ACFT.		Pushback Approved Face North Abeam Stand B6
D7 D9 D11	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing North, then pulled forward until its nosewheel is at the PSN2 point.	CAT D and E ACFT pushing back face South shall use TWY TC.	Pushback Approved PSN2
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing South and continue push until abeam stand D11. Taxi out via TC TWY.		Pushback Approved Face South Abeam Stand D11

PUSHBACK PROCEDURES (CONTD 4)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
B2 C3 C4	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T3 facing South. Taxi out via T5 TWY.	HS4 (Be aware of the ACFT pushbacks from stands B2, B4, C1, C2, C3, C4, D1, D3 and D5).	Pushback Approved Face South on T3 TWY
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY facing West abeam stand C2. Taxi out via T3 TWY.		Pushback Approved Face West
C1 C2 D1 D3 D5	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY facing East abeam stand C3. Taxi out via T5 TWY.	HS4 (Be aware of the ACFT pushbacks from stands B2, B4, C1, C2, C3, C4, D1, D3 and D5).	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T5 facing South abeam stand D7. Taxi out via T3 TWY.		Pushback Approved Face South on T5 TWY
TERMINAL CONTACT APRON - East Cul-de-Sac area			
D12 D14 D16	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing North.	CAT D and E ACFTs pushing back face South shall use TWY TD.	Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing South.		Pushback Approved Face South
D20	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY NE facing West and continue push until TWY T9 will remain clear of ACFT.		Pushback Approved Face West on NE TWY
F12L thru F12R F14	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South.	CAT D and E ACFTs pushing back face South shall use TWY TD.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing North.		Pushback Approved Face North
D6 D8 D10	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing North, then pulled forward until its nosewheel is at the PSN4 point.	CAT D and E ACFTs pushing back face South shall use TWY TD.	Pushback Approved PSN4
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing South and continue push until abeam stand D10.		Pushback Approved Face South Abeam Stand D10
F4L thru F4R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South and continue push until its nosewheel is at the PSN3 point.	HS5 (Be aware of the ACFT pushbacks from stands D2, D4, E1, E2, E3, E4, F2, F4L, F4 and F4R).	Pushback Approved PSN3
F4	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South then pulled forward until its nosewhell is at the PSN 4 on TWY T7 face North.		Pushback Approved PSN4
F4L F4R	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY facing East abeam stand E3. Taxi out via T9 TWY.		Pushback Approved Face East

PUSHBACK PROCEDURES (CONTD 5)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
F6L thru F6R F8L thru F8R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South and continue push until its nosewheel is at the PSN3 point.	HS7 (Be aware of the ACFT pushbacks from stands F6L and F8R)	Pushback Approved PSN3
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing North, then pulled forward until abeam stand F6.	CAT D and E ACFTs pushing back face South shall use TWY TD.	Pushback Approved Face North Abeam Stand F6
D2 D4 E1 E2	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY facing West abeam stand E3. Taxi out via T7 TWY.	HS5 (Be aware of the ACFT pushbacks from stands D2, D4, E1, E2, E3, E4, F2, F4L, F4 and F4R).	Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing South abeam D6. Taxi out via T9 TWY.		Pushback Approved Face South on T7 TWY
E3	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South abeam stand F4. Taxi out via T7 TWY.	HS5 (Be aware of the ACFT pushbacks from stands D2, D4, E1, E2, E3, E4, F2, F4L, F4 and F4R).	Pushback Approved Face South on T9 TWY
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T7 facing South abeam stand D6. Taxi out via T9 TWY.		Pushback Approved Face South on T7 TWY
E4 F2	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T9 facing South abeam stand F4 Taxi out via T7 TWY.	HS5 (Be aware of the ACFT pushbacks from stands D2, D4, E1, E2, E3, E4, F2, F4L, F4 and F4R).	Pushback Approved Face South on T9 TWY
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY facing East abeam stand E3. Taxi out via T9 TWY.		Pushback Approved Face East
TERMINAL CONTACT APRON - Northwest area			
F1L thru F1R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing South and continue push until TWY F6 will remain clear of ACFT.	HS9 (Be aware of the ACFT pushbacks from stands F1L, F1 and G2, G2R).	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing North and continue push until TWY F6 will remain clear of ACFT.		Pushback Approved Face North
F3L thru F3R F5L thru F5R F7L thru F7R F9L thru F9R F13L thru F13R F18 F19	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing South.		Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing North.		Pushback Approved Face North
F15 F16 F17	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY NE facing West.	The ACFT pushing back from Stand F15 should pull forward until T9 TWY is clear.	Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY NE facing East.		Pushback Approved Face East

PUSHBACK PROCEDURES (CONTD 6)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
TERMINAL CONTACT APRON - Southeast area			
G2L thru G2R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing South and continue push until TWY F6 will remain clear of ACFT.	HS9 (Be aware of the ACFT pushbacks from stands F1L, F1 and G2, G2R).	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing North and continue push until TWY F6 will remain clear of ACFT.		Pushback Approved Face North
G4L thru G8R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing South.		Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing North.		Pushback Approved Face North
G9L thru G9R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY F1 facing North and continue push until its nosewheel is at the PSN10 point.	F2 TWY is CAT C.	Pushback Approved PSN10
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing West and continue push until its nosewheel is at the PSN6 point facing South.		Pushback Approved PSN6
G10L thru G11R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing West then following the pushback line onto TWY F1 facing North and continue push until its nosewheel is at the PSN10 point.	F2 TWY is CAT C.	Pushback Approved PSN10
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY T11 facing West and continue push until its nosewheel is at the PSN6 point facing South.		Pushback Approved PSN6
APRON 1			
100 thru 109	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing East.		Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing West.		Pushback Approved Face West
110 thru 121	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing West.		Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing West.		Pushback Approved Face East
122 thru 131	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing West.		Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N6 facing East.		Pushback Approved Face East

PUSHBACK PROCEDURES (CONTD 7)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
132 thru 137R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing East.	The ACFT pushes on a live TWY that may delay other taxiing ACFT.	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing West.		Pushback Approved Face West
138L thru 143R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing East.	The ACFT pushes on a live TWY that may delay other taxiing ACFT.	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing West.		Pushback Approved Face West
144L thru 149	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing West.	The ACFT pushes on a live TWY that may delay other taxiing ACFT.	Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY N5 facing East.		Pushback Approved Face East
APRON 2			
200 thru 207	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face South.		Pushback Approved Face South
215L thru 217R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY E3 to face North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E3 to face South.		Pushback Approved Face South
220L thru 220R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face East.	HS10 (Be aware of the ACFT pushbacks from stands 214 and 220).	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E3 to face South and continue push until D TWY is clear.		Pushback Approved Face South on E3 TWY
221L thru 221R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face East.	E2 TWY is CAT C.	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face West, then pulled forward until abeam stand 221.		Pushback Approved Face West
222L thru 222R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face East.		Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face West.		Pushback Approved Face West

PUSHBACK PROCEDURES (CONTD 8)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
223L thru 223R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face East, then pulled forward until abeam stand 223.		Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face West.		Pushback Approved Face West
224L thru 224R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face South.		Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face West.		Pushback Approved Face West
208 thru 212	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face North.		Pushback Approved Face North
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face South.		Pushback Approved Face South
213, 214	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face East.	HS10 (Be aware of the ACFT pushbacks from stands 214 and 220).	Pushback Approved Face East
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY E2 to face South.		Pushback Approved Face South
218L thru 218R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face North, then pulled forward until its nosewheel is at the PSN7 point.		Pushback Approved PSN7
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face South, then pulled forward until TWY E1 will remain clear of ACFT.		Pushback Approved Face South
219L thru 219R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face North, then pulled forward until its nosewheel is at the PSN7 point.		Pushback Approved PSN7
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY D to face South.		Pushback Approved Face South
APRON 3			
300 thru 312	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY F2 facing South.	Alternate pushback is not suitable for stands 311 and 312.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY F2 facing North.		Pushback Approved Face North
313L thru 315R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY F1 facing South.	The ACFTs pushing back from stands 313L thru 313R should pull forward until TWY T11 is clear.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY F1 facing North.		Pushback Approved Face North

PUSHBACK PROCEDURES (CONTD 9)

STAND	PUSHBACK PROCEDURE	CAUTION	PHRASEOLOGY
316L thru 317R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY F1 facing South and continue push until its nosewheel is at the PSN8 point.	F2 TWY is CAT C.	Pushback Approved PSN8
318L thru 319R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY G facing South and continue push until its nosewheel is at the PSN9 point facing East on G1 TWY.		Pushback Approved PSN9
CARGO 1 THRU 5 APRONS			
K1L thru K9R	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY A4 facing West.		Pushback Approved Face West
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY A4 facing East.		Pushback Approved Face East
K10 thru K21	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY B facing South.	The ACFT pushes on a live TWY that may delay other taxiing ACFT.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY B facing North.		Pushback Approved Face North
K50 thru K57	Standard Pushback: The ACFT shall be pushed back following the pushback line onto TWY A facing South.	The ACFT pushes on a live TWY that may delay other taxiing ACFT.	Pushback Approved Face South
	Alternate Pushback: The ACFT shall be pushed back following the pushback line onto TWY A facing North.		Pushback Approved Face North



16 SEP 22 (31-1)



ISTANBUL, TURKIYE
① ILS Z Rwy 16R

D-ATIS Arrival		YESILKOY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4		Ground 1																																																																																	
126.350		West Final 132.475		West Directory 120.125 132.050		131.1		118.075																																																																																	
126.3		124.725																																																																																							
LOC IUCB		Final Apch Crs		NEDBA		CAT IIIB & IIIA ILS		CAT II & I ILS																																																																																	
110.35		174°		3000' (2781')		Refer to Minimums		Apt Elev 325' Rwy 219'																																																																																	
MISSED APCH: Climb on track 174° (MAX 230 KT). At or above 900' turn RIGHT direct to FM165, turn RIGHT to FM166 and hold at 3000'. Do not turn to FM165 before RWY 16R THR (D0.1 IUCB/D0.8 UHL) or crossing 900', whichever is later. 1 2									3000 090°→←270° 3500 MSA ARP																																																																																
Alt Set: hPa Rwy Elev: 8 hPa Trans level: By ATC Trans alt: 12000'																																																																																									
1. For CAT II and CAT III operations, special aircrew and ACFT certification required. 2. P-RNAV approval required. 3. Radar required. 4. DME required.																																																																																									
CAUTION: 1. ATC will clear the ACFT to the Approach Procedure before IAF (INSTA or DIVDI) for Rwy 16R. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV TRANSITION) for Rwy 16R. 2. Do not engage ILS before Localizer intercept point PEVUD. 3. Descent on the GP below 3000' not permitted until passing NEDBA. 4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used. 5. Simultaneous approach authorized with RWY 17L or RWY 18.																																																																																									
1 FOR MINIMUMS BASED ON MISSED APCH CLIMB GRADIENTS for CAT II ILS MIN 4.3%, for CAT I ILS MIN 2.5% SEE 31-1A. 2 Refer to minimums for missed apch climb gradient.																																																																																									
<table><tr><td colspan="2">PEVUD D14.4 IUCB D13.4 UHL MANDATORY 3000'</td><td colspan="2">NEDBA D8.7 IUCB D7.7 UHL</td><td colspan="2">MIVPA D5.1 IUCB D4.1 UHL GS 1870'</td><td colspan="2">D1.0 IUCB D0.0 UHL GS 530'</td><td colspan="2">TCH 55' Rwy 219'</td></tr><tr><td colspan="2">174°</td><td colspan="2">174°</td><td colspan="2">174°</td><td colspan="2">174°</td><td colspan="2"></td></tr><tr><td colspan="2">5.7</td><td colspan="2">3.6</td><td colspan="2">4.1</td><td colspan="2">0.8</td><td colspan="2"></td></tr></table>										PEVUD D14.4 IUCB D13.4 UHL MANDATORY 3000'		NEDBA D8.7 IUCB D7.7 UHL		MIVPA D5.1 IUCB D4.1 UHL GS 1870'		D1.0 IUCB D0.0 UHL GS 530'		TCH 55' Rwy 219'		174°		174°		174°		174°				5.7		3.6		4.1		0.8																																																					
PEVUD D14.4 IUCB D13.4 UHL MANDATORY 3000'		NEDBA D8.7 IUCB D7.7 UHL		MIVPA D5.1 IUCB D4.1 UHL GS 1870'		D1.0 IUCB D0.0 UHL GS 530'		TCH 55' Rwy 219'																																																																																	
174°		174°		174°		174°																																																																																			
5.7		3.6		4.1		0.8																																																																																			
<table><tr><td colspan="2">Gnd speed-Kts</td><td>120</td><td>140</td><td>160</td><td>180</td><td rowspan="2">ALSF-II REIL PAPI PAPI</td><td rowspan="2">230 KT MAX</td><td rowspan="2">900' ↑</td><td rowspan="2">174° on</td><td rowspan="2">FM165 RT</td></tr><tr><td colspan="2">GS</td><td>3.00°</td><td>637</td><td>743</td><td>849</td><td>955</td></tr><tr><td colspan="2"></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table>										Gnd speed-Kts		120	140	160	180	ALSF-II REIL PAPI PAPI	230 KT MAX	900' ↑	174° on	FM165 RT	GS		3.00°	637	743	849	955																																																														
Gnd speed-Kts		120	140	160	180	ALSF-II REIL PAPI PAPI	230 KT MAX	900' ↑	174° on	FM165 RT																																																																															
GS		3.00°	637	743	849						955																																																																														
<table><tr><td colspan="2">Std/State</td><td colspan="6">STRAIGHT-IN LANDING</td><td colspan="2">CIRCLE-TO-LAND</td></tr><tr><td colspan="2">CAT IIIB ILS MACG MIN 5.0%</td><td colspan="2">CAT IIIA ILS MACG MIN 5.0%</td><td colspan="2">CAT II ILS MACG MIN 5.0%</td><td colspan="4">CAT I ILS MACG MIN 4.2%</td></tr><tr><td colspan="2"></td><td colspan="2">DH 50'</td><td colspan="2">RA 133'</td><td colspan="4">DA(H) 420' (201')</td></tr><tr><td colspan="2"></td><td colspan="2"></td><td colspan="2">DA(H) 330' (111')</td><td colspan="2">FULL</td><td colspan="2">TDZ or CL out</td></tr><tr><td colspan="2"></td><td colspan="2"></td><td colspan="2"></td><td colspan="2">ALS out</td><td colspan="2"></td></tr><tr><td>C</td><td>R75m</td><td>R200m</td><td colspan="2">1 R300m</td><td>R550m</td><td>2 R550m</td><td>R1200m</td><td>Max Kts</td><td>MDA(H)</td></tr><tr><td>D</td><td></td><td></td><td colspan="2"></td><td></td><td></td><td></td><td>180</td><td>1400' (1075') V2400m</td></tr><tr><td></td><td></td><td></td><td colspan="2"></td><td></td><td></td><td></td><td>205</td><td>1400' (1075') V3600m</td></tr></table>										Std/State		STRAIGHT-IN LANDING						CIRCLE-TO-LAND		CAT IIIB ILS MACG MIN 5.0%		CAT IIIA ILS MACG MIN 5.0%		CAT II ILS MACG MIN 5.0%		CAT I ILS MACG MIN 4.2%						DH 50'		RA 133'		DA(H) 420' (201')								DA(H) 330' (111')		FULL		TDZ or CL out								ALS out				C	R75m	R200m	1 R300m		R550m	2 R550m	R1200m	Max Kts	MDA(H)	D								180	1400' (1075') V2400m									205	1400' (1075') V3600m
Std/State		STRAIGHT-IN LANDING						CIRCLE-TO-LAND																																																																																	
CAT IIIB ILS MACG MIN 5.0%		CAT IIIA ILS MACG MIN 5.0%		CAT II ILS MACG MIN 5.0%		CAT I ILS MACG MIN 4.2%																																																																																			
		DH 50'		RA 133'		DA(H) 420' (201')																																																																																			
				DA(H) 330' (111')		FULL		TDZ or CL out																																																																																	
						ALS out																																																																																			
C	R75m	R200m	1 R300m		R550m	2 R550m	R1200m	Max Kts	MDA(H)																																																																																
D								180	1400' (1075') V2400m																																																																																
								205	1400' (1075') V3600m																																																																																
1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.																																																																																									

CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

ISTANBUL, TURKIYE
ILS Z Rwy 16R

Gnd speed-Kts		70	90	100	120	140	160	ALSF-II REIL PAPI PAPI		230 KT MAX	900' ↑	on 174°	FM165 RT
Gs 3.00°		372	478	531	637	743	849						
Std/State		STRAIGHT-IN LANDING										CIRCLE-TO-LAND	
		MACG MIN 4.2% DA(H) 420' (201')					MACG MIN 2.5% DA(H) 490' (271')						
		FULL	TDZ or CL out	ALS out	FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)				
A								100	1400'(1075') V1500m				
B								135	1400'(1075') V1600m				
C								180	1400'(1075') V2400m				
D								205	1400'(1075') V3600m				
1 R750m when a Flight Director or Autopilot or HUD to DA is not used.													

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.



LTFM/IST
ISTANBUL






16 SEP 22 **31-10**

ISTANBUL, TURKIYE
LOC or VOR Rwy 18

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
LOC IUCD 110.95	Final Apch Crs 174°	AVTEQ 4000' (3779')	DA/MDA(H) 720' (499')	Apt Elev 325' Rwy 221'
VOR UHN 109.85				
MISSED APCH: Climb 4000'. Turn LEFT to intercept R-130 UHN to proceed RIZKO, then turn LEFT to intercept R-290 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to RIZKO (D7.1/R-130 UHN) before MAP.				
Alt Set: hPa Rwy Elev: 8 hPa Trans level: By ATC Trans alt: 12000'				
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to KORQU and may be subject to a delaying action.				



RECOMMENDED ALTITUDES	
UHN DME	ALTITUDE
10.0	3880'
9.0	3560'
8.0	3230'
7.0	2910'
6.0	2590'
5.0	2270'
4.0	1950'
3.0	1630'
2.0	1310'
1.0	990'



Gnd speed-Kts	120	140	160	180
Descent Angle	3.00°	637	743	849
MAP at UHN VOR				

Std/State		STRAIGHT-IN LANDING		CIRCLE-TO-LAND	
		CDFA			
		1 DA/MDA(H) 720' (499')			
		ALS out			
C	R1500m			Max Kts	MDA(H)
D	R2300m			180	1400' (1075') V2400m
				205	1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.



© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESEN
16 SEP 22 (31-10)

ISTANBUL, TURKIYE
LOC or VOR Rwy 18

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
LOC IUCD 110.95	Final Apch Crs 174°	AVTEQ 4000' (3779')	DA/MDA(H) 720' (499')	Apt Elev 325' Rwy 221'
VOR UHN 109.85				
MISSED APCH: Climb 4000'. Turn LEFT to intercept R-130 UHN to proceed RIZKO, then turn LEFT to intercept R-290 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to RIZKO (D7.1/R-130 UHN) before MAP.				
Alt Set: hPa Rwy Elev: 8 hPa Trans level: By ATC Trans alt: 12000'				
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to KORQU and may be subject to a delaying action.				



Gnd speed-Kts	70	90	100	120	140	160	HIALS II	230 KT MAX	4000'	UHN
Descent Angle	3.00°	372	478	531	637	743	REIL PAPI			
MAP at UHN VOR										

Std/State					STRAIGHT-IN LANDING					CIRCLE-TO-LAND				
					CDFA									
					1 DA/MDA(H) 720' (499')									
					ALS out									
A	R1500m													
B														
C	R1500m					R2300m								
D														

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.


CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.



LTFM/IST
ISTANBUL

16 SEP 22

31-11

ISTANBUL, TURKIYE
ILS Z Rwy 34L

ISTANBUL, TURKIYE
ILS Z Rwy 34L



Std/State		STRAIGHT-IN LANDING			CIRCLE-TO-LAND	
		ILS				
		DA(H) 525' (200')				
		FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)
A	R550m		I R550m	R1200m	100	1400' (1075') V1500m
B					135	1400' (1075') V1600m
C					180	1400' (1075') V2400m
D					205	1400' (1075') V3600m

1	R750m when a Flight Director or Autopilot or HUD to DA is not used.
---	---


LTFM/IST
ISTANBUL

16 SEP 22

JEPPesen

31-11A

ISTANBUL, TURKIYE
CAT II/III ILS Z Rwy 34L



CHANGES: Country name.

© JEPPesen, 2018, 2022. ALL RIGHTS RESERVED.

ISTANBUL, TURKIYE
ILS Y Rwy 34L

[illegible]

Diagram illustrating the proposed runway extension and taxiway layout. Key features include:

- Runway 325' (TCH 55')
- Taxiway 0.6 (GS 560')
- Taxiway 4.4
- Taxiway 3.3
- Taxiway 5.9
- Taxiway 3000' (MANDATOR)
- Taxiway 3000' (MANDATOR)

The extension is marked with a 354° bearing and a 3000' distance.

Grnd speed-Kts	70	90	100	120	140	160		
Gs 3.00°	372	478	531	637	743	849		

Std/State		STRAIGHT-IN LANDING ILS DA(H) 525' (200')			CIRCLE-TO-LAND	
		FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)
A	R550m	R550m	R1200m	100	1400' (1075')	V1500m
B				135	1400' (1075')	V1600m
C				180	1400' (1075')	V2400m
D				205	1400' (1075')	V3600m

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.



16 SEP 22

JEPPESEN

31-12

ISTANBUL, TURKIYE
ILS Y Rwy 34L

D-ATIS Arrival		YESILKÖY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4		Ground 1	
126.350		132.475 West Final		120.125 West Directory		132.050		131.1	
118.075		126.3		124.725					

LOC IUCA 108.55	Final Apch Crs 354°	ELNUG 3000' (2675')	CAT IIIB & IIIA ILS Refer to Minimums	CAT II & I ILS	Apt Elev 325' Rwy 325'
---------------------------	-------------------------------	-------------------------------	--	----------------	---------------------------

MISSED APCH: Climb 3000'. Climb STRAIGHT AHEAD. At or above 760' turn LEFT to intercept R-266 UHL and proceed FM342, then turn LEFT to intercept R-061 CRL inbound, proceed TACIR and hold. MAX 230 KT. Do not turn to FM342 before Rwy 34L End (D1.8 IUCA/D0.8 UHL) or crossing 760', whichever is later.

Alt Set: hPa Rwy Elev: 12 hPa Trans level: By ATC Trans alt: 12000'

1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to OGIBI and may be subject to a delaying action.

CAUTION:
 1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 34L. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV TRANSITION) for Rwy 34L.
 2. Do not engage ILS before Localizer intercept point OGIBI.
 3. Descent on the GP below 3000' not permitted until passing ELNUG.
 4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
 5. Simultaneous approach authorized with Rwy 35R or Rwy 36.

UPNEW D5.2 IUCA D7.8 UHL GS 1970'	ELNUG D8.5 IUCA D11.1 UHL At 180 KT	OGIBI D14.4 IUCA D17.0 UHL At 205 KT	MANDATORY 3000'
---	---	--	------------------------

D0.8 IUCA D3.4 UHL GS 560'	UPNEW D5.2 IUCA D7.8 UHL GS 1970'	ELNUG D8.5 IUCA D11.1 UHL	OGIBI D14.4 IUCA D17.0 UHL
---	---	--	---

Gnd speed-Kts	120	140	160	180
GS	3.00°	637	743	849

REIL PAPI	ALSF-II PAPI	230 KT MAX	760' ↑
----------------------------	-------------------------------	----------------------	------------------

UHL 110.0 R-266	LT	on	UHL 110.0 R-266
--	-----------	-----------	--



Std/State				STRAIGHT-IN LANDING				CIRCLE-TO-LAND			
CAT IIIB ILS		CAT IIIA ILS		CAT II ILS		CAT I ILS					
				RA 106'		DA(H) 525' (200')					
		DH 50'		DA(H) 425' (100')		FULL		TDZ or CL out		ALS out	
										Max Kts	
										MDA(H)	
C		R75m		R200m		R300m		R550m		R1200m	
D		R75m		R200m		R300m		R550m		R1200m	
										180	
										205	
										1400'(1075') V2400m	
										1400'(1075') V3600m	

1 CAT D without autoland: R350m. **2** R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESEN, 2019, 2022. ALL RIGHTS RESERVED.


N ISTANBUL, TURKIYE
CAT II/III ILS Y Rwy 34L



LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-13)

ISTANBUL, TURKIYE
LOC or VOR Rwy 34L






JEPPESEN
16 SEP 22 **31-13**

ISTANBUL, TURKIYE
LOC or VOR Rwy 34L

D-ATIS Arrival	YESILKOY Approach/Radar West Final West Directory			ISTANBUL Tower 1	ISTANBUL Tower 4	Ground 1	
126.350	132.475	120.125	132.050	131.1	118.075	126.3	124.725
LOC IUCA 108.55	Final Apch Crs 354°		ELNUG 3000' (2675')	DA/MDA(H) 1000' (675')	Apt Elev 325' Rwy 325'		
VOR UHL 110.0							
MISSED APCH: Climbing 3000', proceed to UHL, at UHL turn LEFT and intercept R-266 UHL and proceed FM342, then turn LEFT to intercept R-061 CRL, proceed to TACIR and hold. MAX 230 KT.							
Alt Set: hPa		Rwy Elev: 12 hPa		Trans level: By ATC		Trans alt: 12000'	
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to OGIBI and may be subject to a delaying action.							



Profile view of the runway showing elevation, distance, and various markers. The profile starts at a 2.0 distance marker and rises to a 3.0 distance marker. The elevation at the 3.0 marker is 1970'. The profile continues to a 3.3 distance marker, where the elevation is 3000'. The profile then rises to a 5.9 distance marker, where the elevation is 3540'. The profile ends at a 5.9 distance marker, where the elevation is 3000'. The profile is labeled with 'D4.8 UHL', 'UPNEW', 'ELNUG', and 'OGIBI'. The profile also shows 'TCH 55'', 'Rwy 325'', 'M', and 'MANDATORY'.

Distance Marker	Elevation	Notes
2.0	-	TCH 55', Rwy 325', M
3.0	1970'	D4.8 UHL, LOC: [ML34L], VOR: [MD34L]
3.3	3000'	UPNEW, D7.8 UHL
5.9	3540'	ELNUG, D11.1 UHL
5.9	3000'	OGIBI, D17.0 UHL, MANDATORY

Gnd speed-Kts	120	140	160	180	ALSF-II REIL PAPI </
---------------	-----	-----	-----	-----	---

Std/State		STRAIGHT-IN LANDING CDFA	CIRCLE-TO-LAND
		1 DA/MDA(H) 1000' (675')	
		ALS out	Max Kts MDA(H)
C	R2400m		180 1400' (1075') V2400m
D			205 1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.


ANS OPS



LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-14)

ISTANBUL, TURKIYE
ILS Z Rwy 35R

BRIEFING STRIP™

D-ATIS Arrival	YESILKOY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4	
126.350	East Final 130.3	East Directory 118.950	132.325	131.1	118.075	
Ground 2		Ground 3		Ground 5		
121.8		122.6		121.550		
126.825		126.925		129.625		
LOC IUCE	Final Apch Crs	FRUGO	DA(H)	Apt Elev 325'		
109.55	354°	4000' (3690')	510' (200')	Rwy 310'		
MISSED APCH: Climbing 3000' to LADUX on course 354° (MAX 230 KT), turn LEFT to FM090 and hold.						
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'						
1. P-RNAV approval required. 2. Radar required. 3. DME required.						MSA ARP



Gnd speed-Kts	70	90	100	120	140	160	ALSF-II	230 KT	3000'	LADUX on 354°
GS	3.00°	372	478	531	637	849	REIL PAPI	MAX		

Std/State			STRAIGHT-IN LANDING ILS			CIRCLE-TO-LAND		
			DA(H) 510' (200')			Max Kts		
			FULL	TDZ or CL out	ALS out	MDA(H)		
A						100	1400' (1075') V1500m	
B						135	1400' (1075') V1600m	
C	R550m			R550m	R1200m	180	1400' (1075') V2400m	
D						205	1400' (1075') V3600m	

R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.


© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.



LTFM/IST
ISTANBUL

16 SEP 22 31-14

ISTANBUL, TURKIYE
ILS Z Rwy 35R

BRIEFING STRIP™

D-ATIS Arrival		East Final		YESILKOY Approach/Radar East Directory		ISTANBUL Tower 1		ISTANBUL Tower 4															
126.350		130.3		118.950		132.325		131.1		118.075													
Ground 2				Ground 3				Ground 5															
121.8				126.825				122.6				126.925				121.550				129.625			
LOC IUCE		Final Apch Crs		FRUGO		CAT IIIB & IIIA ILS		CAT II & I ILS		Apt Elev 325'													
109.55		354°		4000' (3690')		Refer to Minimums				Rwy 310'													
MISSED APCH: Climbing 3000' to LADUX on course 354° (MAX 230 KT), turn LEFT to FM090 and hold.																							
Alt Set: hPa				Rwy Elev: 11 hPa				Trans level: By ATC				Trans alt: 12000'											
1. P-RNAV approval required. 2. Radar required. 3. DME required.																							



Gnd speed-Kts	120	140	160	180	ALSF-II	230 KT	3000'	LADUX on 354°
GS	3.00°	637	743	849	955	REIL PAPI	MAX	

Std/State		STRAIGHT-IN LANDING				CIRCLE-TO-LAND	
CAT IIIB ILS		CAT IIIA ILS	CAT II ILS		CAT I ILS		
			RA 97'		DA(H) 510' (200')		
		DH 50'	DA(H) 415' (105')		FULL	TDZ or CL out	ALS out
C	R75m	R200m	1 R300m	R550m	2 R550m	R1200m	Max Kts
D							MDA(H)
							180 1400' (1075') V2400m
							205 1400' (1075') V3600m

1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.


CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22 **31-14A**

ISTANBUL, TURKIYE
CAT II/III ILS Z Rwy 35R



CHANGES: Country name.


© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN

31-15


ISTANBUL, TURKIYE
ILS Y Rwy 35R



LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN
31-15ISTANBUL, TURKIYE
ILS Y Rwy 35R

BRIEFING STRIP™

D-ATIS Arrival	YESILKOY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4	
126.350	East Final 130.3	East Directory 132.325	118.950	131.1	118.075	
Ground 2		Ground 3		Ground 5		
121.8	126.825	122.6	126.925	121.550	129.625	
LOC IUCE	Final Apch Crs	FRUGO	DA(H)	Apt Elev 325'		
109.55	354°	4000' (3690')	510' (200')	Rwy 310'		
MISSED APCH: Climb 3000' STRAIGHT AHEAD to LADUX. At LADUX turn LEFT to intercept R-335 UHM, proceed FM090 and hold. MAX 230 KT.						
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'						
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to GAPDI and may be subject to delaying action.						
					MSA ARP	



Gnd speed-Kts	70	90	100	120	140	160	ALS F-II	230 KT	3000'	LADUX	UHM
GS	3.00°	372	478	531	637	743	REIL PAPI	MAX	↑		R-335
							PAPI				LT

Std/State			STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
			ILS					
			DA(H) 510' (200')					
			FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)	
A						100	1400' (1075')	V1500m
B						135	1400' (1075')	V1600m
C						180	1400' (1075')	V2400m
D						205	1400' (1075')	V3600m

R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESSEN, 2019, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN


31-15A


ISTANBUL, TURKIYE
CAT II/III ILS Y Rwy 35R



LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN
31-16ISTANBUL, TURKIYE
ILS X Rwy 35R

LTFM/IST
ISTANBULJEPPESEN
16 SEP 22 31-16ISTANBUL, TURKIYE
ILS X Rwy 35R


LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN

31-16A


ISTANBUL, TURKIYE
CAT II/III ILS X Rwy 35R





LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-17)

ISTANBUL, TURKIYE
LOC or VOR Rwy 35R

D-ATIS Arrival		YESILKOY Approach/Radar		ISTANBUL Tower 1	ISTANBUL Tower 4
East Final	East Directory				
126.350	130.3	118.950	132.325	131.1	118.075
Ground 2		Ground 3		Ground 5	
121.8	126.825	122.6	126.925	121.550	129.625
LOC IUCE 109.55	Final Apch Crs 354°	FRUGO 4000' (3690')	DA/MDA(H) 1000' (690')	Apt Elev 325' Rwy 310'	
VOR UHM 108.25					
MISSED APCH: Climb 3000' on R-354 UHM to LADUX, at LADUX turn LEFT to intercept R-335 UHM, proceed FM090 and hold. MAX 230 KT.					
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'					
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to GAPDI and may be subject to delaying action.					



Gnd speed-Kts	70	90	100	120	140	160	ALSIF-II REIL PAPI	230 KT MAX	3000'	UHM LADUX on R-354
Descent Angle	3.00°	372	478	531	637	743	849			
MAP at D4.8 UHM										

Std/State		STRAIGHT-IN LANDING		CIRCLE-TO-LAND	
		CDFA			
		DA/MDA(H) 1000' (690')			
		ALS out			
A		R1500m		Max Kts	MDA(H)
B				100	1400' (1075') V1500m
C				135	1400' (1075') V1600m
D				180	1400' (1075') V2400m
				205	1400' (1075') V3600m

VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.



16 SEP 22

31-17

JEPPESEN

ISTANBUL, TURKIYE
LOC or VOR Rwy 35R


D-ATIS Arrival		YESILKOY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4	
East Final 126.350		East Directory 118.950		132.325		131.1	
130.3		118.950		132.325		118.075	
Ground 2		Ground 3		Ground 5			
121.8		122.6		121.550		129.625	
126.825		126.925					
LOC IUCE 109.55		FRUGO 4000' (3690')		DA/MDA(H) 1000' (690')		Apt Elev 325' Rwy 310'	
VOR UHM 108.25		Final Apch Crs 354°					
MISSED APCH: Climb 3000' on R-354 UHM to LADUX, at LADUX turn LEFT to intercept R-335 UHM, proceed FM090 and hold. MAX 230 KT.							
Alt Set: hPa		Rwy Elev: 11 hPa		Trans level: By ATC		Trans alt: 12000'	
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to GAPDI and may be subject to delaying action.							

3000

090° → ← 270°

3500

MSA ARP



RECOMMENDED ALTITUDES	
UHM DME	ALTITUDE
14.0	3940'
13.0	3620'
12.0	3330'
11.0	2980'
10.0	2660'
9.0	2340'
8.0	2030'
7.0	1710'
6.0	1390'
5.0	1070'

Profile view diagram showing the runway (Rwy 310') and taxiway (TCH 55') layout. Key points and distances are marked:

- D4.8 UHM** (LOC: [ML35R], VOR: [MD35R])
- OLGAV** (D7.8 UHM)
- NASVU** (D11.1 UHM)
- FRUGO** (D14.3 UHM)
- GAPDI** (D16.8 UHM)

Distances and angles are indicated:

- 2.0, 3.0, 1960', 3.3, 3.2, 2.5 (horizontal distances)
- 3.00° (angle between D4.8 UHM and NASVU)
- 354° (angle between FRUGO and GAPDI)
- 4000' (distance from FRUGO to GAPDI)

Gnd speed-Kts	120	140	160	180	REIL PAPI ALSIF-II PAPI 230 KT MAX 3000' LADUX on R-354
Descent Angle 3.00°	637	743	849	955	
MAP at D4.8 UHM					

Std/State		STRAIGHT-IN LANDING CDFA	CIRCLE-TO-LAND
		1 DA/MDA(H) 1000' (690')	
		ALS out	Max Kts
C	R2400m		180 1400' (1075') V2400m
D			205 1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

PANS OPS

LTFM/IST
ISTANBUL



JEPPESEN
16 SEP 22 (31-18)

ISTANBUL, TURKIYE
ILS Z Rwy 36

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3 East Directory 118.950 132.325	119.025	118.075	124.425 124.925
LOC IUCC 111.35	Final Apch Crs 354°	KESKN 4000' (3691')	DA(H) 510' (201')	Apt Elev 325' Rwy 309'
MISSED APCH: Climb on track 354° (MAX 230 KT). At or above 760' turn RIGHT direct to FM367, then turn RIGHT to BKZ VOR, turn RIGHT to BOZDE and hold at 4000'. Do not turn to FM367 before Rwy 36 THR (D0.2 IUCC/D2.9 UHN) or crossing 760', whichever is later.				
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'				
1. P-RNAV approval required. 2. Radar required. 3. DME required.				
				MSA ARP

CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
2. Do not engage ILS before Localizer intercept point GUNCE.
3. Descent on the GP below 4000' not permitted until passing KESKN.
4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
5. Simultaneous apch authorized with Rwy 34L or Rwy 35R (for Rwy 35R only available with ILS X apch).



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II	230 KT	760'	354°	FM367
GS	3.00°	372	478	531	637	743	849	REIL PAPI	MAX	on	RT

Std/State			STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
			ILS					
			DA(H) 510' (201')					
			FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)	
A						100	1400' (1075')	V1500m
B						135	1400' (1075')	V1600m
C						180	1400' (1075')	V2400m
D						205	1400' (1075')	V3600m

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name. © JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL



JEPPESSEN
16 SEP 22 31-18

ISTANBUL, TURKIYE
ILS Z Rwy 36


D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925

LOC IUC	Final Apch Crs	KESKN	CAT IIIB & IIIA ILS	CAT II & I ILS	Apt Elev 325'
111.35	354°	4000' (3691')	Refer to Minimums		Rwy 309'

MISSED APCH: Climb on track 354° (MAX 230 KT). At or above 760' turn RIGHT direct to FM367, then turn RIGHT to BKZ VOR, turn RIGHT to BOZDE and hold at 4000'. Do not turn to FM367 before Rwy 36 THR (D0.2 IUCC/D2.9 UHN) or crossing 760', whichever is later.



Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'

1. For CAT II and CAT III operations, special aircrew and ACFT certification required.
2. P-RNAV approval required. 3. Radar required. 4. DME required.



CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
2. Do not engage ILS before Localizer intercept point GUNCE.
3. Descent on the GP below 4000' not permitted until passing KESKN.
4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
5. Simultaneous apch authorized with Rwy 34L or Rwy 35R (for Rwy 35R only available with ILS X apch).



Gnd speed-Kts	120	140	160	180	REIL PAPI	230 KT MAX	760' on 354°	FM367
GS	3.00°	637	743	849	955			

Std/State		STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
CAT IIIB ILS		CAT IIIA ILS	CAT II ILS		CAT I ILS		
			RA 101'		DA(H) 510' (201')		
		DH 50'	DA(H) 410' (101')		FULL	TDZ or CL out	ALS out
C	R75m	R200m	1 R300m		R550m	2 R550m	R1200m
D							
					Max Kts	MDA(H)	
					180	1400' (1075') V2400m	
					205	1400' (1075') V3600m	

1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.


© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22


JEPPESSEN
31-18A

ISTANBUL, TURKIYE
CAT II/III ILS Z Rwy 36





CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

D-ATIS Arrival	YESILKOY Approach/Radar			ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4	
126.350	East Final 130.3	East Directory 118.950 132.325		119.025	118.075	124.425	124.925
LOC IUCC 111.35	Final Apch Crs 354°		KESKN 4000' (3691')	DA(H) 510' (201')	Apt Elev 325' Rwy 309'		
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD, at or above 760' turn RIGHT to intercept R-079 UHN and proceed FM367, then turn RIGHT to intercept R-314 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to FM367 before Rwy 36 End (D1.5 IUCC/D1.2 UHN) or crossing 760', whichever is later.							
Alt Set: hPa		Rwy Elev: 11 hPa		Trans level: By ATC		Trans alt: 12000'	
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to GUNCE and may be subject to a delaying action.							

CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
2. Do not engage ILS before Localizer intercept point GUNCE.
3. Descent on the GP below 4000' not permitted until passing KESKN.
4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
5. Simultaneous apch authorized with Rwy 34L or Rwy 35R (for Rwy 35R only available with ILS X apch).



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II REIL PAPI
---------------	----	----	-----	-----	-----	-----	---


Std/State		STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
		ILS					
		DA(H) 510' (201')					
		FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)	
A					100	1400' (1075')	V1500m
B					135	1400' (1075')	V1600m
C					180	1400' (1075')	V2400m
D					205	1400' (1075')	V3600m
1 R750m when a Flight Director or Autopilot or HUD to DA is not used.							

LTFM/IST
ISTANBUL

16 SEP 22 31-19



ISTANBUL, TURKIYE
ILS Y Rwy 36

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
LOC IUCC 111.35	Final Apch Crs 354°	KESKN 4000' (3691')	CAT IIIB & IIIA ILS Refer to Minimums	CAT II & I ILS Apt Elev 325' Rwy 309'
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD, at or above 760' turn RIGHT to intercept R-079 UHN and proceed FM367, then turn RIGHT to intercept R-314 BKZ, proceed BKZ VOR and hold. MAX 230 KT, Do not turn to FM367 before Rwy 36 End (D1.5 IUCC/D1.2 UHN) or crossing 760', whichever is later.				
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000'				
1. For CAT II and CAT III operations, special aircrew and ACFT certification required. 2. For transitions P-RNAV approval & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to GUNCE and may be subject to a delaying action.				



CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
2. Do not engage ILS before Localizer intercept point GUNCE.
3. Descent on the GP below 4000' not permitted until passing KESKN.
4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
5. Simultaneous apch authorized with Rwy 34L or Rwy 35R (for Rwy 35R only available with ILS X apch).



Gnd speed-Kts	120	140	160	180	REIL PAPI	230 KT MAX	760'	UHN
GS	3.00°	637	743	849	955			on 109.85 R-079

Std/State		STRAIGHT-IN LANDING					CIRCLE-TO-LAND	
CAT IIIB ILS		CAT IIIA ILS	CAT II ILS	CAT I ILS				
			RA 101'	DA(H) 510' (201')				
		DH 50'	DA(H) 410' (101')	FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)
C	R75m	R200m	1 R300m	R550m	2 R550m	R1200m	180	1400' (1075') V2400m
D							205	1400' (1075') V3600m

1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL



JEPPESSEN
16 SEP 22 (31-19A)

ISTANBUL, TURKIYE
CAT II/III ILS Y Rwy 36

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3 East Directory 118.950 132.325	119.025	118.075	124.425 124.925

LOC IUCC 111.35	Final Apch Crs 354°	KESKN 4000' (3691')	CAT IIIB, IIIA & II ILS Refer to Minimums	Apt Elev 325' Rwy 309'	MSA ARP
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD, at or above 760' turn RIGHT to intercept R-079 UHN and proceed FM367, then turn RIGHT to intercept R-314 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to FM367 before Rwy 36 End (D1.5 IUCC/D1.2 UHN) or crossing 760', whichever is later.					
Alt Set: hPa Rwy Elev: 11 hPa Trans level: By ATC Trans alt: 12000' 1. Special aircrew and ACFT certification required. 2. For transitions P-RNAV approval required & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to GUNCE and may be subject to a delaying action.					

CAUTION:
 1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
 2. Do not engage ILS before Localizer intercept point GUNCE.
 3. Descent on the GP below 4000' not permitted until passing KESKN.
 4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
 5. Simultaneous apch authorized with Rwy 34L or Rwy 35R (for Rwy 35R only available with ILS X apch).



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II	230 KT MAX	760'	UHN
GS	3.00°	372	478	531	637	743	849	REIL PAPI	RT on	109.85 R-079

Std/State	STRAIGHT-IN LANDING	
CAT IIIB ILS	CAT IIIA ILS	CAT II ILS
	DH 50'	RA 101' DA(H) 410' (101')
R75m	R200m	R300m
CAT D without autoland: R350m.		

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

ILS Z RWY 16R MINIMUMS

BASED ON:

MISSED APCH CLIMB GRADIENT MIN 4.3%

Std/State		STRAIGHT-IN LANDING
		CAT II ILS RA 185' DA(H) 370' (151')
C	R450m	
D		

MISSED APCH CLIMB GRADIENT MIN 2.5%

Std/State		STRAIGHT-IN LANDING		
		CAT I ILS DA(H) 490' (271')		
		FULL	TDZ or CL out	ALS out
C	R600m		1 R600m	R1300m
D				

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.


LTFM/IST
ISTANBUL

JEPPESEN

16 SEP 22


(31-1A)


ISTANBUL, TURKIYE
CAT II/III ILS Z Rwy 16R



CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBULJEPPESEN
16 SEP 22 31-2ISTANBUL, TURKIYE
ILS Y Rwy 16R


LTFM/IST
ISTANBULJEPPESEN
16 SEP 22 31-20ISTANBUL, TURKIYE
LOC or VOR Rwy 36

LTFM/IST
ISTANBUL



JEPPESSEN
16 SEP 22 (31-20)

ISTANBUL, TURKIYE
LOC or VOR Rwy 36

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
LOC IUC	Final Aptch Crs	KESKN	DA/MDA(H)	Apt Elev 325'
111.35	354°	4000' (3691')	1000' (691')	Rwy 309'
VOR UHN				
109.85				
MISSED APCH: Climbing 4000', proceed to UHN VOR, at UHN VOR turn RIGHT to intercept R-079 UHN and proceed FM367, then turn RIGHT to intercept R-314 BKZ, proceed BKZ VOR and hold. MAX 230 KT.				
Alt Set: hPa	Rwy Elev: 11 hPa	Trans level: By ATC	Trans alt: 12000'	
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to GUNCE and may be subject to a delaying action.				



CAUTION:
1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV transition) for Rwy 36.
2. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II	230 KT	4000'	UHN	FM367
Descent Angle	3.00°	372	478	531	637	743	849	REIL PAPI	MAX	109.85	RT
MAP at D4.9 UHN											

Std/State	STRAIGHT-IN LANDING	CIRCLE-TO-LAND
	CDFA	
	1 DA/MDA(H) 1000' (691')	
	ALS out	Max Kts
A	R1500m	100 1400' (1075') V1500m
B		135 1400' (1075') V1600m
C	R2400m	180 1400' (1075') V2400m
D		205 1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

ILS Y RWY 16R MINIMUMS

BASED ON:

MISSED APCH CLIMB GRADIENT MIN 4.3%

Std/State		STRAIGHT-IN LANDING
		CAT II ILS
		RA 185'
		DA(H) 370' (151')
C	R450m	
D		

MISSED APCH CLIMB GRADIENT MIN 2.5%

Std/State		STRAIGHT-IN LANDING		
		CAT I ILS		
		DA(H) 490' (271')		
		FULL	TDZ or CL out	ALS out
C	R600m	1 R600m	R1300m	
D				

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.


LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN

31-2A

ISTANBUL, TURKIYE
CAT II/III ILS Y Rwy 16R




CHANGES: Country name.

© JEPPESSEN, 2019, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESEN
16 SEP 22 (31-3)

ISTANBUL, TURKIYE
LOC or VOR Rwy 16R



CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL



16 SEP 22 31-3

JEPPESSEN

ISTANBUL, TURKIYE
LOC or VOR Rwy 16R





16 SEP 22 (31-4)

ISTANBUL, TURKIYE
ILS Z Rwy 17L


D-ATIS Arrival	East Final	YESILKOY Approach/Radar East Directory	ISTANBUL Tower 1	ISTANBUL Tower 4
126.350	130.3	118.950 132.325	131.1	118.075
Ground 2		Ground 3		Ground 5
121.8	126.825	122.6	126.925	121.550 129.625
LOC IUCF	Final ApcH Crs	ELNIN	CAT IIIB & IIIA ILS CAT II & I ILS	Apt Elev 325' Rwy 202'
111.95	174°	4000' (3798')	Refer to Minimums	
MISSED APCH: Climbing 4000' to NASVU on course 174° (MAX 230 KT), turn RIGHT to ERWAZ and hold.				
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'				
1. For CAT II and CAT III operations, special aircrew and ACFT certification required. 2. P-RNAV approval required. 3. RADAR required. 4. DME required.				

3000

090° → ← 270°

3500

MSA ARP



The profile view diagram illustrates the vertical alignment of the runway approach. The horizontal axis represents distance in miles (2.5, 3.1, 3.7, 4.4, 5.0), and the vertical axis represents elevation in feet. The diagram shows the runway threshold at 55 feet, the runway end at 202 feet, and the approach slope at 174 degrees. Obstacle data is provided for TIGSU, ELNIN, LADUX, and ATBES, including their MUF, UHF, and GS values.

Obstacle	MUF	UHF	GS
TIGSU	D14.4	IUCF	D13.6
ELNIN	D11.9	IUCF	D11.1
LADUX	D8.8	IUCF	D8.0
ATBES	D5.1	IUCF	D4.3

Gnd speed-Kts	120	140	160	180	
GS 3.00°	637	743	849	955	

Std/State		STRAIGHT-IN LANDING					CIRCLE-TO-LAND	
CAT IIIB ILS		CAT IIIA ILS	CAT II ILS	CAT I ILS			Max Kts	MDA(H)
			RA 109'	DA(H) 402' (200')				
		DH 50'	DA(H) 303' (101')	FULL	TDZ or CL out	ALS out		
C	R75m	R200m	1 R300m	R550m	2 R550m	R1200m	180	1400' (1075') V2400m
D							205	1400' (1075') V3600m

1 CAT D without autoland: R350m. **2** R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-4)

ISTANBUL, TURKIYE
ILS Z Rwy 17L

BRIEFING STRIP™



D-ATIS Arrival 126.350	East Final 130.3	YESILKOY Approach/Radar East Directory 118.950 132.325	ISTANBUL Tower 1 131.1	ISTANBUL Tower 4 118.075
Ground 2 121.8 126.825		Ground 3 122.6 126.925		Ground 5 121.550 129.625
LOC IUCF 111.95	Final Apch Crs 174°	ELNIN 4000' (3798')	DA(H) 402' (200')	Apt Elev 325' Rwy 202'
MISSED APCH: Climbing 4000' to NASVU on course 174°, (MAX 230 KT), turn RIGHT to ERWAZ and hold.				
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'				
1. P-RNAV approval required. 2. RADAR required. 3. DME required.				

3000

090° → ← 270°

3500

MSA ARP



Gnd speed-Kts	70	90	100	120	140	160	ALSF-II REIL PAPI	230 KT MAX	NASVU on 174°	ERWAZ RT
GS	3.00°	372	478	531	637	743	849			

Std/State		STRAIGHT-IN LANDING ILS			CIRCLE-TO-LAND	
		DA(H) 402' (200')				
		FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)
A					100	1400' (1075') V1500m
B					135	1400' (1075') V1600m
C	R550m		R550m	R1200m	180	1400' (1075') V2400m
D					205	1400' (1075') V3600m

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL


16 SEP 22

JEPPESSEN



31-4A

ISTANBUL, TURKIYE
CAT II/III ILS Z Rwy 17L

BRIEFING STRIP™

D-ATIS Arrival 126.350	East Final 130.3	YESILKOY Approach/Radar East Directory 118.950	132.325	ISTANBUL Tower 1 131.1	ISTANBUL Tower 4 118.075
Ground 2 121.8 126.825		Ground 3 122.6 126.925		Ground 5 121.550 129.625	
LOC IUCF 111.95	Final Apch Crs 174°	ELNIN 4000' (3798')	CAT IIIB, IIIA & II ILS Refer to Minimums	Apt Elev 325' Rwy 202'	
MISSED APCH: Climbing 4000' to NASVU on course 174°, (MAX 230 KT), turn RIGHT to ERWAZ and hold.					
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'					
1. Special aircrew and acft certification required. 2. P-RNAV approval required. 3. RADAR required. 4. DME required.					

MSA ARP



Gnd speed-Kts	70	90	100	120	140	160	ALSF-II	230 KT	NASVU	174°	ERWAZ
GS	3.00°	372	478	531	637	743	REIL PAPI	MAX	on		RT

Std/State	STRAIGHT-IN LANDING	
CAT IIIB ILS	CAT IIIA ILS	CAT II ILS
	DH 50'	RA 109' DA(H) 303' (101')
R75m	R200m	1 R300m
1 CAT D without autoland: R350m.		

CHANGES: Country name.


© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-5)

ISTANBUL, TURKIYE
ILS Y Rwy 17L

D-ATIS Arrival	East Final	YESILKOY Approach/Radar	ISTANBUL Tower 1	ISTANBUL Tower 4
126.350	130.3	East Directory	131.1	118.075
Ground 2	Ground 3	Ground 5		
121.8	126.825	122.6	126.925	121.550
LOC	Final	ELNIN	DA(H)	Apt Elev 325'
IUCF	Apch Crs			Rwy 202'
111.95	174°	4000' (3798')	402' (200')	
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.				
Alt Set: hPa	Rwy Elev: 7 hPa	Trans level: By ATC	Trans alt: 12000'	
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.				
				MSA ARP



TIGSU	ELNIN	LADUX	ATBES	D0.7 IUCF	
D14.4 IUCF	D11.9 IUCF	D8.8 IUCF	D5.1 IUCF	D0.1 UHM	
D13.6 UHM	D11.1 UHM	D8.0 UHM	D4.3 UHM		
MANDATORY 4000'	174°	174°	GS 1850'	GS 430'	
2.5	3.1	3.7	4.4	0.6	
					TCH 55'
					Rwy 202'

Gnd speed-Kts	70	90	100	120	140	160		ALSIF-II			
GS	3.00°	372	478	531	637	743	849	REIL	PAPI	230 KT	NASVU
										MAX	↑

Std/State	STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
	ILS					
	DA(H) 402' (200')					
	FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)	
A				100	1400' (1075')	V1500m
B				135	1400' (1075')	V1600m
C	R550m	R550m	R1200m	180	1400' (1075')	V2400m
D				205	1400' (1075')	V3600m

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESSEN, 2019, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22 31-5

JEPPESSEN

ISTANBUL, TURKIYE
ILS Y Rwy 17L

D-ATIS Arrival		YESILKOY Approach/Radar		ISTANBUL Tower 1		ISTANBUL Tower 4			
East Final		East Directory							
126.350		130.3		118.950		132.325			
131.1						118.075			
Ground 2			Ground 3			Ground 5			
121.8			126.825			122.6			
126.925			121.550			129.625			
LOC IUCF		Final Apch Crs		ELNIN		CAT IIIB & IIIA ILS		CAT II & I ILS	
111.95		174°		4000' (3798')		Apt Elev 325'		Rwy 202'	
				Refer to Minimums					
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.									
Alt Set: hPa		Rwy Elev: 7 hPa		Trans level: By ATC		Trans alt: 12000'			
1. For CAT II and CAT III operations, special aircrew and ACFT certification required. 2. For transitions P-RNAV approval & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.									


3000

090°

270°

3500

MSA ARP



TIGSU	ELNIN	LADUX	ATBES	D0.7 IUCF	TCH 55'
D14.4 IUCF	D11.9 IUCF	D8.8 IUCF	D5.1 IUCF	D0.1 UHM	Rwy 202'
D13.6 UHM	D11.1 UHM	D8.0 UHM	D4.3 UHM	GS 430'	
MANDATORY 4000'	174° 4000'	174°	GS 1850'		
2.5	3.1	3.7	4.4	0.6	

Gnd speed-Kts	120	140	160	180	ALSIF-II	230 KT	NASVU
GS	3.00°	637	743	849	REIL PAPI	MAX	↑

Std/State		STRAIGHT-IN LANDING				CIRCLE-TO-LAND	
CAT IIIB ILS		CAT IIIA ILS	CAT II ILS		CAT I ILS	Max Kts MDA(H)	
		DH 50'	RA 109'		DA(H) 402' (200')		
			DA(H) 303' (101')		FULL TDZ or CL out ALS out		
C	R75m	R200m	1 R300m	R550m	2 R550m	R1200m	180 1400' (1075') V2400m
D							205 1400' (1075') V3600m

1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESSEN, 2019, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL



16 SEP 22

JEPPESSEN

(31-5A)

ISTANBUL, TURKIYE
CAT II/III ILS Y Rwy 17L

D-ATIS Arrival	East Final	YESILKOY Approach/Radar	ISTANBUL Tower 1	ISTANBUL Tower 4
126.350	130.3	118.950	132.325	131.1
121.8	126.825	122.6	126.925	121.550
LOC IUCF 111.95	Final Apch Crs 174°	ELNIN 4000' (3798')	CAT IIIB, IIIA & II ILS Refer to Minimums	Apt Elev 325' Rwy 202'
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.				
Alt Set: hPa	Rwy Elev: 7 hPa	Trans level: By ATC	Trans alt: 12000'	
1. Special aircrew and ACFT certification required. 2. For transitions P-RNAV approval & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.				
				3000 090° → ← 270° 3500 MSA ARP



Gnd speed-Kts	70	90	100	120	140	160		ALSIF-II	230 KT	NASVU
GS	3.00°	372	478	531	637	743	849	REIL PAPI	MAX	↑

Std/State	STRAIGHT-IN LANDING	
CAT IIIB ILS	CAT IIIA ILS	CAT II ILS
	DH 50'	RA 109'
		DA(H) 303' (101')
R75m	R200m	R300m

1 CAT D without Autoland: R350m.

CHANGES: Country name.

© JEPPESSEN, 2019, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL



16 SEP 22 **31-6**


ISTANBUL, TURKIYE
ILS X Rwy 17L

D-ATIS Arrival 126.350	East Final 130.3	YESILKOY Approach/Radar East Directory 118.950	132.325	ISTANBUL Tower 1 131.1	ISTANBUL Tower 4 118.075
Ground 2 121.8 126.825		Ground 3 122.6 126.925		Ground 5 121.550 129.625	
LOC IUCF 111.95	Final Apch Crs 174°	LADUX 3000' (2798')	CAT IIIB & IIIA ILS Refer to Minimums	CAT II & I ILS Apt Elev 325'	Rwy 202'
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.					
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'					
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.					



CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (INSTA or DIVDI) for Rwy 17L. As soon as such an instruction is received, the ACFT shall completely follow the procedure (including the P-RNAV TRANSITION) for Rwy 17L.
2. Do not engage ILS before Localizer intercept point TIGSU.
3. Descent on the GP below 3000' not permitted until passing LADUX.
4. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.
5. Simultaneous approach authorized with RWY 18.



Gnd speed-Kts	120	140	160	180	ALSIF-II REIL PAPI	230 KT NASVU MAX
GS	3.00°	637	743	849	PAPI	

Std/State		STRAIGHT-IN LANDING				CIRCLE-TO-LAND	
C	CAT IIIB ILS	CAT IIIA ILS	CAT II ILS RA 109'	CAT I ILS DA(H) 402' (200')			Max Kts
		DH 50'	DA(H) 303' (101')	FULL	TDZ or CL out	ALS out	MDA(H)
R75m	R200m		1 R300m	R550m	2 R550m	1200m	180 1400' (1075') V2400m
D							205 1400' (1075') V3600m

1 CAT D without autoland: R350m. **2** R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.



© JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-6)

ISTANBUL, TURKIYE
ILS X Rwy 17L

D-ATIS Arrival 126.350	East Final 130.3	YESILKOY Approach/Radar East Directory 118.950 132.325	ISTANBUL Tower 1 131.1	ISTANBUL Tower 4 118.075
Ground 2 121.8 126.825		Ground 3 122.6 126.925		Ground 5 121.550 129.625
LOC IUCF 111.95	Final Apch Crs 174°	LADUX 3000' (2798')	DA(H) 402' (200')	Apt Elev 325' Rwy 202'
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.				
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'				
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.				



Gnd speed-Kts	70	90	100	120	140	160	ALSF-II REIL PAPI	230 KT NASVU MAX
GS	3.00°	372	478	531	637	743	849	

Std/State	STRAIGHT-IN LANDING ILS			CIRCLE-TO-LAND		
	DA(H) 402' (200')			Max Kts		
	FULL	TDZ or CL out	ALS out	100	1400' (1075')	V1500m
A				135	1400' (1075')	V1600m
B				180	1400' (1075')	V2400m
C				205	1400' (1075')	V3600m
D						

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

16 SEP 22

JEPPESSEN

31-6A

ISTANBUL, TURKIYE
CAT II/III ILS X Rwy 17L



BRIEFING STRIP™	D-ATIS Arrival		East Final		YESILKOY Approach/Radar East Directory		ISTANBUL Tower 1		ISTANBUL Tower 4		
	126.350		130.3		118.950 132.325		131.1		118.075		
	Ground 2			Ground 3				Ground 5			
	121.8 126.825			122.6 126.925				121.550 129.625			
	LOC IUCF		Final Apch Crs		LADUX		CAT IIIB, IIIA & II ILS Refer to Minimums		Apt Elev 325' Rwy 202'		
	111.95		174°		3000' (2798')						
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD to NASVU, at NASVU turn RIGHT on 264° to intercept R-200 UHM, proceed to ERWAZ and hold. MAX 230 KT.											
Alt Set: hPa Rwy Elev: 7 hPa Trans level: By ATC Trans alt: 12000'											
1. Special aircrew and ACFT certification required. 2. For transitions P-RNAV approval & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to TIGSU and may be subject to a delaying action.											

3000

090° → ← 270°

3500

MSA ARP



Gnd speed-Kts	70	90	100	120	140	160	ALSF-II REIL PAPI	230 KT	NASVU
GS	3.00°	372	478	531	637	743	849	MAX	↑

Std/State	STRAIGHT-IN LANDING		
CAT IIIB ILS	CAT IIIA ILS	CAT II ILS	
	DH 50'	RA 109'	
		DA(H) 303' (101')	
R75m	R200m	R300m	

1 CAT D without Autoland: R350m.


CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-7)

ISTANBUL, TURKIYE
LOC or VOR Rwy 17L




CHANGES: Country name.

© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.



LTFM/IST
ISTANBUL

JEPPESEN

16 SEP 22 (31-7)

ISTANBUL, TURKIYE
LOC or VOR Rwy 17L


D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
LOC IUCD	Final Apt Crs	AVTEQ	CAT IIIB & IIIA ILS	Apt Elev 325'
110.95	174°	4000' (3779')	Refer to Minimums	Rwy 221'
MISSED APCH: Climb on track 174° (MAX 230 KT). At or above 760' turn LEFT direct to FM187, turn LEFT to ENLEC and hold at 4000'. Do not turn to FM187 before RWY 18 THR (D0.2 IUCD/D1.2 UHN) or crossing 760', whichever is later. Refer to minimums for missed apch climb gradient.				
Alt Set: hPa	Rwy Elev: 8 hPa	Trans level: By ATC	Trans alt: 12000'	
1. P-RNAV approval required. 2. RADAR required. 3. DME required.				



Gnd speed-Kts	120	140	160	180	HIALS-II	230 KT	760'	FM187
GS	3.00°	637	743	849	REIL PAPI	MAX	on 174°	LT

Std/State		STRAIGHT-IN LANDING				CIRCLE-TO-LAND		
C	CAT IIIB ILS	CAT IIIA ILS	CAT II ILS		CAT I ILS		Max Kts	MDA(H)
	MACG MIN 3.5%	MACG MIN 3.5%	MACG MIN 3.5%	MACG MIN 2.5%	DA(H) 421'(200')	DA(H)		
		DH 50'	RA 104'	RA 127'	FULL	TDZ or CL out		
			321'(100')	336'(115')		ALS out		
C	R75m	R200m	R300m	R300m	R550m	R550m	180	1400'(1075')V2400m
D						R1200m	205	1400'(1075')V3600m

1 CAT D without autoland: R350m. 2 R750m when a Flight Director or Autopilot or HUD to DA is not used.





LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-8A)

ISTANBUL, TURKIYE
CAT II/III ILS Z RWY 18

D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	118.950 132.325	119.025	118.075 124.425 124.925
LOC IUCD 110.95	Final Apch Crs 174°	AVTEQ 4000' (3779')	CAT IIIB, IIIA & II ILS Refer to Minimums	Apt Elev 325' Rwy 221'
MISSED APCH: Climb on track 174° (MAX 230 KT). At or above 760' turn LEFT direct to FM187, turn LEFT to ENLEC and hold at 4000'. Do not turn to FM187 before RWY 18 THR (D0.2 IUCD/D1.2 UHN) or crossing 760', whichever is later. Refer to minimums for missed apch climb gradient.				
Alt Set: hPa	Rwy Elev: 8 hPa	Trans level: By ATC	Trans alt: 12000'	MSA ARP
1. Special aircrew and ACFT certification required. 2. P-RNAV approval required. 3. RADAR required. 4. DME required.				




Gnd speed-Kts							70	90	100	120	140	160	HIALS-II REIL PAPI <
---------------	--	--	--	--	--	--	----	----	-----	-----	-----	-----	--


Std/State			
STRAIGHT-IN LANDING			
CAT IIIB ILS	CAT IIIA ILS	CAT II ILS	
MACG MIN 3.5%	MACG MIN 3.5%	MACG MIN 3.5%	MACG MIN 2.5%
	DH 50'	RA 104' DA(H) 321' (100')	RA 127' DA(H) 336' (115')
R75m	R200m	R300m	R300m



1 CAT D without Autoland: R350m.

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.



D-ATIS Arrival	YESILKOY Approach/Radar		ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4	
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075	124.425 124.925	
LOC IUCD 110.95	Final Apch Crs 174°	AVTEQ 4000' (3779')	DA(H) 421' (200')	Apt Elev 325' Rwy 221'		
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD, at or above 760' turn LEFT on 084° to intercept R-130 UHN and proceed RIZKO, then turn LEFT to intercept R-290 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to RIZKO before Rwy 18 end (D1.4 IUCD/D2.8 UHL) or crossing 760' whichever is later.						
Alt Set: hPa Rwy Elev: 8 hPa Trans level: By ATC Trans alt: 12000'						
1. For transitions P-RNAV approval & Radar required. 2. VOR/DME required. 3. Non P-RNAV ACFT will be radar vectored to KORQU and may be subject to a delaying action.						



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II		230 KT	760'	084°
GS	3.00°	372	478	531	637	743	REIL PAPI		MAX	↑	LT

Std/State		STRAIGHT-IN LANDING			CIRCLE-TO-LAND		
		ILS					
		DA(H) 421' (200')					
		FULL	TDZ or CL out	ALS out	Max Kts	MDA(H)	
A					100	1400' (1075') V1500m	
B					135	1400' (1075') V1600m	
C	R550m		R550m	R1200m	180	1400' (1075') V2400m	
D					205	1400' (1075') V3600m	

1 R750m when a Flight Director or Autopilot or HUD to DA is not used.


CHANGES: Country name.



© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (31-9A)

ISTANBUL, TURKIYE
CAT II/III ILS Y RWY 18

D-ATIS Arrival	YESILKOY Approach/Radar		ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
East Final	East Directory				
126.350	130.3	118.950 132.325	119.025	118.075	124.425 124.925
LOC IUCD 110.95	Final Apch Crs 174°	AVTEQ 4000' (3779')	CAT IIIB, IIIA & II ILS Refer to Minimums	Apt Elev 325' Rwy 221'	 MSA ARP
MISSED APCH: Climb to 4000'. Climb STRAIGHT AHEAD, at or above 760' turn LEFT on 084° to intercept R-130 UHN and proceed RIZKO, then turn LEFT to intercept R-290 BKZ, proceed BKZ VOR and hold. MAX 230 KT. Do not turn to RIZKO before Rwy 18 end (D1.4 IUCD /D2.8 UHL) or crossing 760' whichever is later. Refer to minimums for missed apch climb gradient.					
Alt Set: hPa Rwy Elev: 8 hPa Trans level: By ATC Trans alt: 12000'					
1. Special aircrew and aircraft certification required. 2. For transitions P-RNAV approval & Radar required. 3. VOR/DME required. 4. Non P-RNAV ACFT will be radar vectored to KORQU and may be subject to a delaying action.					



Gnd speed-Kts	70	90	100	120	140	160
GS	3.00°	372	478	531	637	849


Std/State				STRAIGHT-IN LANDING			
CAT IIIB ILS MACG MIN 3.5%		CAT IIIA ILS MACG MIN 3.5%		CAT II ILS MACG MIN 3.5%		CAT II ILS MACG MIN 2.5%	
		DH 50'		RA 104' DA(H) 321' (100')		RA 127' DA(H) 336' (115')	
R75m		R200m		R300m		R300m	

CHANGES: Country name. © JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.

LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (32-1)

ISTANBUL, TURKIYE
RNP Rwy 16R



CHANGES: Country name.


© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL


JEPPESEN

16 SEP 22 (32-1)

ISTANBUL, TURKIYE
RNP Rwy 16R










LTFM/IST
ISTANBUL

JEPPESEN
16 SEP 22 (32-3)

ISTANBUL, TURKIYE
RNP Rwy 18


D-ATIS Arrival	YESILKOY Approach/Radar	ISTANBUL Tower 5	ISTANBUL Tower 4	ISTANBUL Ground 4
126.350	East Final 130.3	East Directory 118.950 132.325	119.025	118.075 124.425 124.925
RNAV	Final Apch Crs 174°	AVTEQ MANDATORY 4000' (3779')	LNAV/VNAV DA(H) 720' (499')	Apt Elev 325' Rwy 221'
MISSED APCH: Climb on track 174° (MAX 190 KT), at or above 760' turn LEFT direct to FM187, turn LEFT to ENLEC and hold at 4000'. Do not turn to FM187 before MAP or crossing 760', whichever is later.				
Alt Set: hPa	Rwy Elev: 8 hPa	Trans level: By ATC	Trans alt: 12000'	
1. RNP apch approval required. 2. GNSS required. 3. Baro VNAV operations not authorized below -20°C and above 40°C. 4. Timing not authorized for defining MAP.				



Gnd speed-Kts	70	90	100	120	140	160	HIALS-II	190 KT MAX	760' on 174°	FM187
Descent Angle	3.00°	372	478	531	637	743	REIL PAPI			
MAP at MA18										
AVTEQ to MAP	10.3	8:50	6:52	6:11	5:09	4:25	3:52			

Std/State				STRAIGHT-IN LANDING				CIRCLE-TO-LAND			
LNAV/VNAV				LNAV CDFA							
DA(H) 720' (499')				1 DA/MDA(H) 720' (499')							
ALS out				ALS out							
A	R1500m			R1500m			Max Kts	MDA(H)			
B	R1500m			R1500m			100	1400' (1075') V1500m			
C	R1500m			R1500m			135	1400' (1075') V1600m			
D	R1500m			R1500m			180	1400' (1075') V2400m			
							205	1400' (1075') V3600m			

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.
CHANGES: Country name. © JEPPESEN, 2020, 2022. ALL RIGHTS RESERVED.




LTFM/IST
ISTANBUL




JEPPESSEN


16 SEP 22 32-4

ISTANBUL, TURKIYE
RNP Rwy 34L

D-ATIS Arrival	YESILKOY Approach/Radar		ISTANBUL Tower 1	ISTANBUL Tower 4	Ground 1	
126.350	West Final 132.475	West Directory 120.125 132.050	131.1	118.075	126.3	124.725
RNAV	Final Apch Crs 354°	ELNUG MANDATORY 3000' (2675')	LNAV/VNAV DA(H) 900' (575')	Apt Elev 325' Rwy 325'		
MISSED APCH: Climb on track 354° (MAX 210 KT), at or above 1200' turn LEFT direct to FM342, turn LEFT to FM736 and hold at 3000'. Do not turn to FM342 before MAP or crossing 1200', whichever is later.						
Alt Set: hPa Rwy Elev: 12 hPa Trans level: By ATC Trans alt: 12000'						
1. RNP apch approval required. 2. GNSS required. 3. Baro VNAV operations not authorized below -20°C and above 40°C. 4. Timing not authorized for defining MAP.						



RECOMMENDED ALTITUDES	
DIST to RW34L	ALTITUDE
8.0	2930'
7.0	2610'
6.0	2290'
5.0	1970'
4.0	1650'
3.0	1330'
2.0	1010'



Gnd speed-Kts	120	140	160	180
Descent Angle	3.00°	637	743	849
MAP at RW34L				
ELNUG to MAP	8.3	4:09	3:33	3:07

Std/State		STRAIGHT-IN LANDING		CIRCLE-TO-LAND	
LNNAV/VNAV		LNNAV CDFA			
DA(H) 900' (575')		DA/MDA(H) 1000' (675')			
ALS out		ALS out			
C	R1900m	R2400m	R2400m	Max Kts	MDA(H)
D				180	1400' (1075') V2400m
				205	1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.


CHANGES: Country name.


© JEPPESSEN, 2018, 2022. ALL RIGHTS RESERVED.


LTFM/IST
ISTANBUL

JEPPESSEN
16 SEP 22 (32-5)

ISTANBUL, TURKIYE
RNP Rwy 35R








LTFM/IST
ISTANBUL



JEPPESSEN
16 SEP 22 32-6



ISTANBUL, TURKIYE
RNP Rwy 36

D-ATIS Arrival	YESILKOY Approach/Radar			ISTANBUL Tower 5		ISTANBUL Tower 4		ISTANBUL Ground 4	
126.350	East Final 130.3	East Directory 118.950 132.325		119.025		118.075		124.425 124.925	
RNAV	Final Apch Crs 354°		KESKN MANDATORY 4000' (3691')		LNAV/VNAV DA(H) 800' (491')		Apt Elev 325' Rwy 309'		
MISSED APCH: Climb on track 354° (MAX 190 KT), at or above 1100' turn RIGHT direct to FM367, turn RIGHT to BKZ VOR, turn RIGHT to BOZDE and hold at 4000'. Do not turn to FM367 before MAP or crossing 1100', whichever is later.									
Alt Set: hPa		Rwy Elev: 11 hPa		Trans level: By ATC		Trans alt: 12000'			
1. RNP apch approval required. 2. GNSS required. 3. Baro VNAV operations not authorized below 20°C and above 40°C. 4. Timing not authorized for defining the MAP.									

CAUTION:

1. ATC will clear the ACFT to the Approach Procedure before IAF (IMREN or SADIK) for Rwy 36. As soon as such an instruction is received, the ACFT shall completely follow the procedure for Rwy 36.
2. ACFT unable to conform to speed restrictions shall inform ATC and state what speeds to be used.

RECOMMENDED ALTITUDES	
DIST to RW36	ALTITUDE
11.0	3860'
10.0	3540'
9.0	3220'
8.0	2910'
7.0	2590'
6.0	2270'
5.0	1950'
4.0	1630'
3.0	1310'
2.0	1000'



Gnd speed-Kts	120	140	160	180	HIALS-II	190 KT MAX	1100'	354°	FM367
Descent Angle	3.00°	637	743	849	955	REIL PAPI			
MAP at RW36									
KESKN to MAP	11.4	5:42	4:53	4:17	3:48				

Std/State		STRAIGHT-IN LANDING		CIRCLE-TO-LAND	
LNNAV/VNAV		LNNAV CDFA			
DA(H) 800' (491')		DA/MDA(H) 1000' (691')			
ALS out		ALS out		Max Kts	
C	R1500m	R2300m	R2400m	180	1400' (1075') V2400m
D				205	1400' (1075') V3600m

1 VNAV DA(H) in lieu of MDA(H) depends on operator policy.

CHANGES: Country name.

© JEPPESSEN, 2020, 2022. ALL RIGHTS RESERVED.